

## **BID NOTICE**

Notice is hereby given to all Bidders that the Bristol Kendall Fire Protection District will be accepting sealed bids for a Tanker Fire Apparatus. The apparatus will have a 3000 gallon water tank with a 1000 gallon per minute pump built on a commercial chassis.

Contract Documents may be obtained through the Fire Protection District at: 103 East Beaver Street; Yorkville, Illinois 60560; 630-553-6186 beginning January 13, 2017.

There will be no Pre-Bid Meeting.


Sealed bids will be received until 2:00 p.m. on February 6, 2017. At such time, bids will be opened at the Bristol Kendall Fire Protection District Station No 1, 103 East Beaver Street; Yorkville, Illinois 60560, and read out loud. All bids shall be valid for at least 60 days.

General questions may be directed to Fire Chief Michael Hitzemann or Assistant Chief Timothy Fairfield at 630-553-6186

All bidders will be required to certify that they are in compliance with laws governing bid-rigging, bid rotation, equal opportunity employment and sexual harassment and are not barred from contracting with any unit of state or local government.

The Bristol Kendall Fire Protection District Board of Trustees reserves the right to reject any bid, or portion thereof, or to waive minor deviations from the bid documents, if it deems it is in the public interest to do so.

Published January 16, 2017 in the *Beacon News*.



## Bristol Kendall Fire Protection District

103 East Beaver Street  
Yorkville, IL 60560-1704  
Phone: 630 553-6186  
Fax: 630 553-1482

January 12, 2017

The Board of Trustees of the Bristol Kendall Fire Protection District is accepting sealed bids for a tanker fire apparatus.

It is the intent of these specifications to cover the building, furnishing, and delivery of a tanker fire apparatus to the Bristol Kendall Fire Protection District, meeting all provisions of the National Fire Protection Association, Pamphlet # 1901, latest edition, as well as all applicable Federal Motor Vehicle Safety Standards.

The attached specifications shall have each paragraph marked with an "X" in the appropriate column, indicating "YES" compliance with that paragraph, or "NO" not in compliance with that paragraph. Any paragraph marked with a "NO" indicates that an exception is being taken. All exceptions taken to these specifications shall be listed, by page number and paragraph, on a separate page titled "EXCEPTIONS", along with an explanation of the exception and what is to be supplied in lieu of the specified item.

Each bid shall be accompanied by the included "Bid Proposal Sheet", the attached specifications, with all paragraphs marked as stated above, along with a detailed proposal describing the apparatus and equipment, which the bidder proposes to build.

Each bid shall be accompanied by a "Bid Bond", as described in these specifications.

Upon delivery of the apparatus, the successful bidder will be required to supply, two (2) copies of a complete maintenance construction manual, documentation that axle weights are within the axle manufacturers limits, and verification and/or certification that all requirements listed in these specification have been met.

The Bristol Kendall Fire Protection District is a tax-exempt institution, and all bids should be calculated on this basis.


The Bristol Kendall Fire Protection District is a member of the HGACBuy Cooperative Purchasing Consortium. Member number 16-5750. Appropriate discounts should be included in the bid package.

**Completed and properly signed bids must be received by the Bristol Kendall Fire Protection District no later than 2:00 p.m., Monday, February 6, 2017.** Sealed bids will be opened at this time, at the Bristol Kendall Fire Station, # 1, 103 East Beaver Street, Yorkville, Illinois. Approval of the successful bidder should be made by The Board of Trustees of the Bristol Kendall Fire Protection District at their regular meeting on February 9, 2017 at 5:00 p.m.

Envelopes are to be sealed and clearly marked: "**TANKER BID**" All bids not hand delivered are to be sent to: Bristol Kendall Fire Protection District

103 East Beaver Street  
Yorkville, IL 60560-1704

All question regarding these specifications or bid requirements shall be directed to:  
Chief Michael Hitzemann - 630-553-6186 Extension # 101, or Assistant Chief Timothy  
Fairfield - 630-553-6186 Extension # 103



# Bristol Kendall Fire Department

103 East Beaver Street  
Yorkville, IL 60560-1704  
Phone: 630 553-6186

## BID PROPOSAL SHEET

### FOR 3000 GALLON TANKER

APPARATUS MANUFACTURER \_\_\_\_\_

COMPANY NAME \_\_\_\_\_

COMPANY ADDRESS \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP CODE \_\_\_\_\_

BID PRICE F.O.B. YORKVILLE, ILLINOIS: \$ \_\_\_\_\_

AFTER RECEIPT OF ORDER, DELIVERY WITHIN \_\_\_\_\_ CALENDAR DAYS

NAME & PHONE NUMBER, INCLUDING AREA CODE, OF INDIVIDUAL TO CONTACT DURING BUSINESS HOURS. NAME \_\_\_\_\_

PHONE # \_\_\_\_\_ - \_\_\_\_\_

NAME & PHONE NUMBER, INCLUDING AREA CODE, OF INDIVIDUAL TO CONTACT EVENINGS. NAME \_\_\_\_\_

PHONE # \_\_\_\_\_ - \_\_\_\_\_

NAME OF PERSON SUBMITTING BID (PRINTED) \_\_\_\_\_

SIGNATURE OF PERSON SUBMITTING BID \_\_\_\_\_

TITLE OF PERSON SUBMITTING BID \_\_\_\_\_

DATE \_\_\_\_\_ - \_\_\_\_\_ - \_\_\_\_\_

Bidder Complies	
Yes	No

**SPECIFICATIONS FOR A 3000 GALLON CAPACITY TANKER**

**INTENT OF SPECIFICATIONS**

It shall be the intent of these specifications to cover the furnishing and delivery of a complete fire apparatus. These detailed specifications cover the requirements as to the type of construction and test to which the apparatus shall conform, together with certain details as to finish, equipment and appliances with which the successful bidder shall conform. Minor details of construction and materials, which are not otherwise specified, are left to the discretion of the contractor. The manufacturer shall provide loose equipment only when specified by the customer. Otherwise, in accordance with the current edition of NFPA 1901 standards, the proposal shall specify whether the fire department or apparatus dealership shall provide required loose equipment.

In order to ensure fair, ethical, and legal competition, neither original equipment manufacturer (O.E.M.) or parent company of the O.E.M. shall have ever been fined or convicted of price fixing, bid rigging, or collusion in any domestic or international fire apparatus market (no exception).

Bids shall only be considered from companies that have an established reputation in the field of fire apparatus construction and have been in business for a minimum of 20 years. Further, bidder shall maintain dedicated service facilities for the repair and service of products. Evidence of such a facility shall be included in bidder proposal.

Each bidder shall furnish satisfactory evidence of their ability to construct the apparatus specified and shall state the location of the factory where the apparatus is to be built. The bidder shall also show that the company is in position to render prompt service and to furnish replacement parts.

Each bid shall be accompanied by a detailed set of Contractor's Specifications consisting of a detailed description of the apparatus and equipment proposed, and to which the apparatus furnished under contract shall conform. These specifications shall indicate size, type, model and make of all component parts and equipment

Images and illustrative material in this specification are as accurate as known at the time of publication, but are subject to change without notice. Images and illustrative material is for reference only, and may include optional equipment and accessories and may not include all standard equipment.

Bidder Complies	
Yes	No

**QUALITY AND WORKMANSHIP**

The design of the apparatus shall embody the latest approved automotive engineering practices. The workmanship shall be of the highest quality in its respective field. Special consideration shall be given to the following points: Accessibility of the various units which require periodic maintenance; ease of operation (including both pumping and driving); and symmetrical proportions. Construction shall be rugged and ample safety factors shall be provided to carry the loads specified and to meet both on and off road requirements and speed conditions as set forth under Performance Tests and Requirements. Welding shall not be employed in the assembly of the apparatus in a manner that shall prevent the ready removal of any component part for service or repair. All steel welding shall follow American Welding Society D1.1-2004 recommendations for structural steel welding. All aluminum welding shall follow American Welding Society and ANSI D1.2-2003 requirements for structural welding of aluminum. All sheet metal welding shall follow American Welding Society B2.1-2000 requirements for structural welding of sheet metal. Flux core arc welding to use alloy rods, type 7000, American Welding Society standards A5.20-E70T1. Employees classified as welders are tested and certified to meet American Welding Society codes upon hire and every three (3) years thereafter.

**DELIVERY**

Apparatus, to insure proper break in of all components while still under warranty, **shall be delivered under its own power** - rail or truck freight shall not be acceptable. A qualified delivery engineer representing the contractor shall deliver the apparatus and remain for a sufficient length of time to instruct personnel in the proper operation, care and maintenance of the equipment delivered.

**INFORMATION REQUIRED**

The manufacturer shall supply at time of delivery, complete operation and maintenance manuals covering the completed apparatus as delivered. A permanent plate shall be mounted in the driver's compartment which specifies the quantity and type of fluids required including engine oil, engine coolant, transmission, pump transmission lubrication, pump primer and drive axle.

**SAFETY VIDEO**

Documentation provided at the time of delivery shall also include an apparatus safety video, in DVD format. This video shall address key safety considerations for personnel to follow when they are driving, operating, and maintaining the apparatus. Safety procedures for the following shall be included: vehicle pre-trip inspection, chassis operation, pump operation, and maintenance.

**PERFORMANCE TESTS AND REQUIREMENTS**

A road test shall be conducted with the apparatus fully loaded and a continuous run of ten (10) miles or more shall be made under all driving conditions, during which time the apparatus shall

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

Bidder Complies	
Yes	No

show no loss of power or overheating. The transmission drive shaft or shafts, and rear axles shall run quietly and be free from abnormal vibration or noise throughout the operating range of the apparatus. Vehicle shall adhere to the following parameters:

- A) The apparatus, when fully equipped and loaded, shall have not less than 25 percent nor more than 50 percent of the weight on the front axle, and not less than 50 percent nor more than 75 percent on the rear axle.
- B) The apparatus shall be capable of accelerating to 35 mph from a standing start within 25 seconds on a level concrete highway without exceeding the maximum governed rpm of the engine.
- C) The service brakes shall be capable of stopping a fully loaded vehicle in 35 feet at 20 mph on a level concrete highway. The air brake system shall conform to Federal Motor Vehicle Safety Standards (FMVSS) 121.
- D) The apparatus, fully loaded, shall be capable of obtaining a speed of 50 mph on a level concrete highway with the engine not exceeding its governed rpm (full load).

**FAILURE TO MEET TEST**

In the event the apparatus fails to meet the test requirements of these specifications on the first trial, second trials may be made at the option of the bidder within 30 days of the date of the first trial. Such trials shall be final and conclusive and failure to comply with these requirements shall be cause for rejection. Failure to comply with changes to conform to any clause of the specifications, within 30 days after notice is given to the bidder of such changes, shall also be cause for rejection of the apparatus. Permission to keep or store the apparatus in any building owned or occupied by the purchaser or its use by the purchaser during the above-specified period with the permission of the bidder shall not constitute acceptance.

**LIABILITY**

The successful bidder shall defend any and all suits and assume all liability for the use of any patented process including any device or article forming a part of the apparatus or any appliance furnished under the contract.

**SPECIFICATION BID REQUIREMENTS**

Bidders shall also indicate in the "yes/no" column if their bid complies **on each item** (PARAGRAPH) specified. Exceptions shall be allowed if they are equal to or superior to that specified and provided they are listed and fully explained on a separate page.

**Proposals taking total exception to specifications shall not be acceptable.**

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>Also, bidders shall submit a detailed proposal. A letter only, even though written on a company letterhead, shall not be sufficient. Bid proposals shall be submitted in the same sequence as specifications for ease of evaluation, comparison and checking of compliance. <b>An exception to these requirements shall not be tolerated.</b></p> <p><b><u>EXCEPTIONS</u></b> All exceptions shall be stated no matter how seemingly minor. Any exceptions not taken shall be assumed by the purchaser to be included in the proposal, regardless of the cost to the bidder.</p> <p><b><u>GENERAL CONSTRUCTION</u></b> The apparatus shall be designed with due consideration to distribution of load between the front and rear axles. Weight balance and distribution shall be in accordance with the recommendations of the National Fire Protection Association.</p> <p><b><u>COMMERCIAL GENERAL LIABILITY INSURANCE</u></b> The successful bidder shall, during the performance of the contract and for three (3) years following acceptance of the product, keep in force at least the following minimum limits of commercial general liability insurance:</p> <p style="padding-left: 40px;">Each Occurrence\$1,000,000</p> <p style="padding-left: 40px;">Products/Completed Operations Aggregate\$1,000,000</p> <p style="padding-left: 40px;">Personal and Advertising Injury\$1,000,000</p> <p style="padding-left: 40px;">General Aggregate\$5,000,000</p> <p>Coverage shall be written on a Commercial General Liability form. The policy shall be written on an occurrence form and shall include Contractual Liability coverage for bodily injury and property damage subject to the terms and conditions of the policy. The policy shall include Owner as an additional insured when required by written contract.</p> <p><b><u>COMMERCIAL AUTOMOBILE LIABILITY INSURANCE</u></b> The successful bidder shall, during the performance of the contract keep in force at least the following minimum limits of commercial automobile liability insurance:</p> <p style="padding-left: 40px;">Each Accident Combined Single Limit:\$1,000,000</p> <p>Coverage shall be written on a Commercial Automobile liability form.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>UMBRELLA/EXCESS LIABILITY INSURANCE</u></b></p> <p>The successful bidder shall, during the performance of the contract and for three (3) years following acceptance of the product, keep in force at least the following minimum limits of umbrella liability insurance:</p> <p style="padding-left: 40px;">Aggregate:\$25,000,000</p> <p style="padding-left: 40px;">Each Occurrence:\$25,000,000</p> <p>The umbrella policy shall be written on an occurrence basis and at a minimum provide excess to the Bidder's General Liability, Automobile Liability and Employer's Liability policies.</p> <p>The required limits can be provided by one (1) or more policies provided all other insurance requirements are met.</p> <p>Coverage shall be provided by a carrier(s) rated A- or better by A.M. Bests.</p> <p>All policies shall provide a 30 day notice of cancellation to the named insured. The Certificate of Insurance shall provide the following cancellation clause: Should any of the above described policies be cancelled before the expiration date thereof, notice shall be delivered in accordance with the policy provisions. Bidder agrees to furnish owner with a current Certificate of Insurance with the coverages listed above along with its bid. The certificate shall show the purchaser as certificate holder.</p> <p><b><u>ISO COMPLIANCE</u></b></p> <p>The manufacturer shall operate a Quality Management System under the requirements of ISO 9001. These standards sponsored by the International Organization for Standardization (ISO) specify the quality systems that shall be established by the manufacturer for design, manufacture, installation and service. A copy of the certificate of compliance shall be included with the bid.</p> <p>The bidder shall state the location of the factory where the apparatus is to be built.</p> <p><b><u>NFPA 2016 STANDARDS</u></b></p> <p>This apparatus specification includes a commercial chassis that has not been certified to meet the requirements of NFPA 1901 by the chassis manufacturer. Although this chassis may comply with certain aspects of the standard, has not received certification from this chassis manufacturer that all criteria have been met. The body as built by the manufacturer must comply with the NFPA standards effective January of 2016.</p> <p>Certification of slip resistance of all stepping, standing and walking surfaces must be supplied with delivery of the apparatus.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>All horizontal surfaces designated as a standing or walking surface that are greater than 48.00" above the ground must be defined by a 1.00" wide line along its outside perimeter. Perimeter markings and designated access paths to destination points shall be identified on the customer approval print and are shown as approximate. Actual location(s) shall be determined based on materials used and actual conditions at final build. Access paths may pass through hose storage areas and opening or removal of covers or restraints may be required. Access paths may require the operation of devices and equipment such as the aerial device or ladder rack.</p> <p>A plate that is highly visible to the driver while seated shall be provided. This plate shall show the overall height, length, and gross vehicle weight rating.</p> <p>The manufacturer shall have programs in place for training, proficiency testing and performance for any staff involved with certifications.</p> <p>An official of the company shall designate, in writing, who is qualified to witness and certify test results.</p> <p><b><u>NFPA COMPLIANCY</u></b></p> <p>Apparatus proposed by the bidder shall meet the applicable requirements of the National Fire Protection Association (NFPA) as stated in the current edition at time of contract execution. Fire Department's specifications that differ from NFPA specifications shall be indicated in the proposal as "non-NFPA."</p> <p><b><u>PUMP TEST</u></b></p> <p>The rated water pump shall be tested, approved, and certified by an ISO certified independent third party testing agency at the manufacturer's expense. The test results, along with the pump manufacturer's certification of hydrostatic test, the engine manufacturer's certified brake horsepower curve, and the manufacturer's record of pump construction details shall be forwarded to the Fire Department.</p> <p><b><u>REQUIREMENTS OF THE APPARATUS MANUFACTURER</u></b></p> <p>The manufacturer of the apparatus must be fully owned and managed by a Parent Company, Corporation, Partnership, or that is a company 100% held in the United States of America.</p> <p>Proposals from any manufacturer that is fully or partially owned and/or operated by a Foreign Company, Corporation, Partnership, or that is a company under any type of ownership, partnership, or any similar type of agreement shall be rejected immediately and their bid disqualified. (NO EXCEPTIONS).</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

Bidder Complies	
Yes	No

**INSPECTION TRIP(S) PRICED AS AN OPTION**

The bidder shall provide one (1) factory inspection trip(s) for 2 members of the Bristol Kendall FPD as designated by the chief customer representative(s). The inspection trip(s) shall be scheduled at times mutually agreed upon between the manufacturer's representative and the customer. All costs such as travel, lodging and meals shall be the responsibility of the bidder.

**TABLE OF CONTENTS**

A table of contents shall be provided with all proposals, for ease in locating items which shall be provided by the bidder.

**AFTERMARKET SUPPORT WEBSITE**

A Customer Service website shall provide authorized dealers access to comprehensive information pertaining to the maintenance and service of their customer's apparatus. This tool shall provide the authorized dealer the ability to service and support their customers to the best of their ability with factory support at their fingertips.

This website shall also be accessible to the end user through the guest login. Limited access is available and vehicle specific parts information accessible by entering a specific VIN number. All end users should see their local authorized dealer for additional support and service.

The website shall provide the following to the designated individuals:

- Authorized dealer only - ability to access truck detail information on the major components of the vehicle, warranty information, available vehicle photographs, vehicle drawings, sales options, applicable vehicle software downloads, etc.
- Authorized dealer and customer - parts look-up capability, with the aid of digital photographs, part drawings, and assembly drawings.
- Authorized dealer only - ability to electronically submit warranty claims directly to the factory for reimbursement.
- Authorized dealer only - accessibility to multiple dealer reports that allow the dealership to maintain communication with the customer on the status of orders, claims, and phone contacts.
- Authorized dealer and customer - access to all currently published Operation and Maintenance and Service publications.
- Authorized dealer only - access to manufacturer Service Bulletins and Work Instructions containing information on current service topics and recommendations provided.

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

Bidder Complies	
Yes	No

- Authorized dealer and customer - access to upcoming training classes offered by the manufacturer.
- Authorized dealer only - access to interactive electronic learning modules (Operators Guides) covering the operation of major vehicle components.
- Authorized dealer only - access to customer service articles, corporate news, quarterly newsletters, and key contacts.

**BID BOND**

All bidders shall provide a bid bond as security for the bid in the form of a 10% bid bond to accompany their bid. This bid bond shall be issued by a Surety Company who is listed on the U.S. Treasury Departments list of acceptable sureties as published in Department Circular 570. The bid bond shall be issued by an authorized representative of the Surety Company and shall be accompanied by a certified power of attorney dated on or before the date of bid. The bid bond shall include language, which assures that the bidder/principal shall give a bond or bonds as may be specified in the bidding or contract documents, with good and sufficient surety for the faithful performance of the contract, including the Basic One (1) Year Limited Warranty, and for the prompt payment of labor and material furnished in the prosecution of the contract.

Notwithstanding any document or assertion to the contrary, any surety bond related to the sale of a vehicle shall apply only to the Basic One (1) Year Limited Warranty for such vehicle. Any surety bond related to the sale of a vehicle shall not apply to any other warranties that are included within this bid (OEM or otherwise) or to the warranties (if any) of any third party of any part, component, attachment or accessory that is incorporated into or attached to the vehicle. In the event of any contradiction or inconsistency between this provision and any other document or assertion, this provision shall prevail.

**PERFORMANCE BOND**

Notwithstanding any document or assertion to the contrary, any surety bond related to the sale of a vehicle shall apply only to the Basic One (1) Year Limited Warranty for such vehicle. Any surety bond related to the sale of a vehicle shall not apply to any other warranties that are included within this bid (OEM or otherwise) or to the warranties (if any) of any third party of any part, component, attachment or accessory that is incorporated into or attached to the vehicle. In the event of any contradiction or inconsistency between this provision and any other document or assertion, this provision shall prevail.

**REFERENCE DRAWING**

A drawing of the proposed apparatus shall be provided for review. This drawing shall indicate the major components such as the chassis make and model, body configuration and door style, location of the lights, siren, horns, compartments, major components, etc.

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>This drawing shall not need to be signed and returned to the apparatus manufacturer.</p> <p><b><u>ELECTRICAL WIRING DIAGRAMS</u></b> Two (2) electrical wiring diagrams, prepared for the body as it interfaces with the commercial chassis, shall be provided.</p> <p><b><u>CHASSIS</u></b> The chassis shall be a Freightliner, Model M2, 106MD Conventional Chassis, supplied with the following equipment:</p> <p><b><u>WHEELBASE</u></b> The wheelbase of the vehicle shall be no greater than 210".</p> <p><b><u>GVW RATING</u></b> The gross vehicle weight rating shall be a minimum of 54,600 lbs.</p> <p><b><u>FRAME</u></b> The frame rails shall be formed from 120,000 psi yield, heat treated alloy steel.</p> <p><b><u>FRONT AXLE</u></b> Front axle shall be an I beam type, made of forged steel with a ground rating capacity of 14,600 lb.</p> <p><b><u>FRONT SUSPENSION</u></b></p> <ul style="list-style-type: none"> <li>- Spring mounted</li> <li>- Capacity at Ground: 14,600 lb.</li> <li>- Shock Absorbers: Double Acting</li> </ul> <p>Shock absorbers shall be provided on the front axle.</p> <p><b><u>TIRES, FRONT</u></b> Front tires shall be Michelin 12R22.50, radial tires with a tread pattern suitable for the steering axle position. The capacity of the tires shall meet or exceed the rating of the axle and/or suspension.</p> <p><b><u>WHEELS, FRONT</u></b> Wheels for the front axle shall be 22.50" x 8.25" aluminum disc, ten (10)-hole pattern.</p> <p><b><u>REAR AXLE</u></b> The rear axle shall be a tandem axle assembly with a capacity of 40,000 lb.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>An inter-axle differential, which divides torque evenly between axles, shall be provided with an indicator light mounted on the cab instrument panel.</p> <p><b><u>REAR AXLE RATIO</u></b> A rear axle ratio shall be furnished to allow the vehicle to reach a top speed of 60 MPH.</p> <p><b><u>SUSPENSION, REAR</u></b> Rear suspension to be the Freightliner flat steel spring system. Ground rating of the suspension to be 40,000 lbs. Axles to have 52.00" spacing.</p> <p><b><u>TIRES, REAR</u></b> Rear tires shall be Michelin 11R22.50 radial tires with a traction tread pattern suitable for the drive axle position. The tires shall meet or exceed the weight rating of the axle and/or suspension.</p> <p><b><u>WHEELS, REAR</u></b> The rear wheels shall be 22.50" x 8.25" disc with a ten (10)-hole pattern. The outer wheel shall be polished aluminum and the inner wheel shall be steel. An insulating ring shall be placed between the steel wheel and the aluminum wheel to prevent corrosion between the dissimilar metals.</p> <p><b><u>TIRE PRESSURE MANAGEMENT</u></b> There shall be a VECSAFE LED tire alert pressure management system provided that shall monitor each tire's pressure. A chrome plated brass sensor shall be provided on the valve stem of each tire for a total of 10 tires.</p> <p>The sensor shall calibrate to the tire pressure when installed on the valve stem for pressures between 20 and 120 psi. The sensor shall activate an integral battery operated LED when the pressure of that tire drops 8 psi.</p> <p>Removing the cap from the sensor shall indicate the functionality of the sensor and battery. If the sensor and battery are in working condition, the LED shall immediately start blinking.</p> <p><b><u>FRONT HUB COVERS</u></b> Stainless steel hub covers shall be provided on the front axle. An oil level viewing window shall be provided.</p> <p><b><u>REAR HUB COVERS</u></b> Stainless steel, high hat, hub covers shall be provided on the rear axle hubs.</p> <p><b><u>CHROME LUG NUT COVERS</u></b> Chrome lug nut covers shall be supplied on front and rear wheels.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>MUD FLAPS</u></b> Mud flaps shall be installed behind the front and rear wheels of the apparatus. The mud flaps shall be black.</p> <p><b><u>WHEEL CHOCKS PROVIDED BY THE APPRATUS MANUFACTURER OR DEALER</u></b> NFPA 1901, 2016 edition, section 7.9.4 requires two (2) or more wheel chocks mounted in readily accessible locations that together shall hold the apparatus, when loaded to its GVWR or GCWR, on a hard surface with a 20 percent grade with the transmission in neutral and the parking brake released. There will be one (1) pair of folding Ziamatic SAC-44-E, aluminum alloy, Quick-Choc wheel blocks, with easy-grip handle provided.</p> <p><b><u>WHEEL CHOCK BRACKETS, PROVIDED BY THE APPRATUS MANUFACTURER OR DEALER</u></b> The wheel chock brackets shall be provided and installed by the apparatus manufacturer or dealer. Location of the brackets to be confirmed by the District at the appropriate time during the construction / delivery process. There will be one (1) pair of Ziamatic SQCH-44-H horizontal mounting wheel chock brackets provided for the Ziamatic SAC-44-E folding wheel chocks.</p> <p><b><u>ANTI-LOCK BRAKE SYSTEM</u></b> The vehicle shall be equipped with a Wabco, model 4S/4M, four (4) channel anti-lock braking system. The ABS shall provide anti-lock braking control on both the front and rear wheels. It shall be a digitally controlled system that utilizes microprocessor technology to control the anti-lock braking system. Each wheel shall be monitored by the system. When any particular wheel begins to lockup, a signal shall be sent to the control unit. This control unit then shall reduce the braking of that wheel for a fraction of a second and then reapply the brake. This anti-lock brake system shall eliminate the lockup of any wheel thus helping to prevent the apparatus from skidding out of control.</p> <p>The system shall include Automatic Traction Control (ATC).</p> <p>The system shall include Electronic Stability Control (ESC). When instability is detected, the ESC system shall automatically apply brakes to individual wheels (with no intervention from the driver) and may also reduce engine torque to help keep the vehicle on track.</p> <p><b><u>FRONT BRAKES</u></b> The front brakes shall be S-Cam, 16.50" x 5.00". The front brakes shall be provided with Meritor™ automatic slack adjusters.</p> <p><b><u>AIR COMPRESSOR, BRAKE SYSTEM</u></b> The air compressor shall be a Wabco with 18.7 cubic feet per minute output.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>AIR DRYER</u></b>                      A Bendix AD-9SI air dryer with a heater shall be provided. Other features of this air dryer include:</p> <ul style="list-style-type: none"> <li>- Desiccant style filter</li> <li>- In-line filtration system</li> <li>- Automatic purge valve</li> </ul> <p><b><u>ENGINE</u></b></p> <ul style="list-style-type: none"> <li>• Model: Electronic Cummins ISL-300</li> <li>• Number of Cylinders: Six (6)</li> <li>• Bore and Stroke: 4.49" x 5.69"</li> <li>• Displacement: 543 cubic inches (8.9 Liter)</li> <li>• Rated Brake Horsepower: 350 at 2000 rpm</li> <li>• Peak Torque: 1000 at 1400 rpm</li> <li>• Governed rpm: 2200</li> <li>• Turbocharger</li> <li>• Charge Air Cooled</li> <li>• Fuel System: Hydraulically Actuated, Electronically Controlled Unit Injectors (HEUI)</li> </ul> <p><b><u>ENGINE ACCESSORIES</u></b></p> <ul style="list-style-type: none"> <li>• Air Cleaner: Dry type, with restriction indicator in cab</li> <li>• Fuel Filters: Dual, with check valve</li> <li>• Governor: Limiting speed type</li> <li>• Lube Oil Cooler</li> <li>• Lube Oil Filter: Full flow</li> <li>• Starting Motor: 12-volt</li> <li>• Oil Fill and Level Gauge</li> </ul> <p><b><u>RADIATOR</u></b></p> <ul style="list-style-type: none"> <li>• Pressurized System, Tube and Fin</li> <li>• Deaeration Tank and Sight Glass</li> <li>• Anti-Freeze Protection -30 Degrees Fahrenheit</li> </ul> <p><b><u>HIGH IDLE</u></b>                      A high idle switch shall be provided on the instrument panel inside the cab. Activating the switch shall cause the vehicle to automatically maintain a preset engine rpm.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>The high idle switch shall be operational only when the parking brake is on and the truck transmission is in neutral. A green indicator light shall be provided adjacent to the switch. The light shall be labeled "OK To Engage High Idle."</p> <p><b><u>ENGINE EXHAUST BRAKE</u></b></p> <p>An exhaust brake with an integral variable geometry turbo charger (VGT) shall be provided. The control shall be located on the instrument panel within easy reach of the driver. When this brake engages, it shall also automatically command the transmission to downshift into 4th gear, providing additional braking performance.</p> <p><b><u>AIR INTAKE, W/EMBER SEPARATOR</u></b></p> <p>The air inlet shall be equipped with a stainless steel mesh to separate water and burning embers from the air intake system such that particulate matter larger than 0.039" (1.0 mm) in diameter cannot reach the air filter element.</p> <p>This shall comply with NFPA 1901 and 1906 standards.</p> <p><b><u>EXHAUST SYSTEM</u></b></p> <p>The exhaust system shall include a diesel particulate filter (DPF) and a selective catalytic reduction (SCR) device to meet current EPA standards. The DPF and SCR shall be mounted horizontally outside of the frame rails in the passenger side front step area.</p> <p><b><u>EXHAUST MODIFICATIONS</u></b></p> <p>The exhaust shall terminate the right side of the body with a horizontal tailpipe and diffuser ahead of the passenger side rear wheels.</p> <p>A heat deflector shield shall be provided where the tail pipe is routed under any side compartmentation.</p> <p><b><u>COOLANT LINES</u></b></p> <p>Gates Blue Stripe rubber hose shall be used for all engine coolant lines installed by the chassis manufacturer.</p> <p>Hose clamps shall be of a design commonly called constant torque type to prevent coolant leakage. They shall react to temperature changes in the cooling system and expand or contract accordingly while maintaining a constant clamping pressure on the hose.</p> <p><b><u>FUEL TANK</u></b></p> <p>A 50 gallon fuel tank shall be provided and mounted at the left-hand cab step. The rectangular tank shall be constructed of aluminum.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>DIESEL EXHAUST FLUID TANK</u></b>                      A 6.00 gallon diesel exhaust fluid (DEF) tank shall be provided and mounted on the driver's side, below the cab.</p> <p>The tank shall include an integrated heater unit that utilizes engine coolant to thaw the DEF in the event of freezing.</p> <p><b><u>FUEL PRIMER PUMP</u></b>                      A fuel primer pump shall be included with the fuel water separator.</p> <p><b><u>AUXILIARY FUEL COOLING SYSTEM</u></b>                      A supplementary fuel cooling system shall be provided to allow the use of water from the discharge side of the pump for cooling the chassis engine fuel. The heat exchanger shall be a cylindrical type and shall be a separate unit. The cooler shall operate any time the pump is discharging water and shall be plumbed to the master drain valve.</p> <p><b><u>TRANSMISSION</u></b>                      An Allison, model 3000 EVS, electronic torque converting automatic transmission shall be provided.</p> <p>Two (2) PTO openings shall be located on left side and top of converter housing (positions 8 o'clock and 4 o'clock).</p> <p>A transmission temperature gauge or warning light shall be installed on cab instrument panel.</p> <p><b><u>TRANSMISSION SHIFT CONTROL</u></b>                      A push button shift module shall be mounted to right of driver. Shift position indicator shall be indirectly lit for after dark operation.</p> <p>The transmission shall be a five (5)-speed.</p> <p><b><u>TRANSMISSION COOLER</u></b>                      A transmission oil cooler shall be provided in the lower tank of the radiator.</p> <p><b><u>DRIVELINE</u></b>                      Drivelines shall be a heavy duty metal tube equipped with universal joints properly sized for the application. A splined slip joint shall be provided in each driveshaft.</p> <p><b><u>STEERING</u></b>                      The steering system shall be hydraulically driven. The steering column shall have an adjustable tilt and telescope feature.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>BUMPER</u></b> A 14.00", three (3) piece, full width chrome plated steel bumper with collapsible boxed ends shall be attached to the front of the chassis frame.</p> <p><b><u>TOW HOOKS</u></b> Two (2) painted, forged steel tow hooks shall installed under the bumper and attached to the front frame member..</p> <p><b><u>BUMPER GAP</u></b> The standard bumper furnished with the chassis shall be used.</p> <p><b><u>CAB</u></b> A 2-door flat-roof cab shall be provided. The cab and doors shall be of an aluminum construction.</p> <p><b>Exterior Styling</b></p> <p>Aerodynamic hood and windshield</p> <p>Tinted Glass in all Windows</p> <p>Fiberglass hood with mounted plastic grille</p> <p>Single 63"x14" rear window</p> <p><b>Interior</b></p> <p>Leaf spring rear cab suspension</p> <p>Vinyl mats</p> <p>Forward roof mounted console</p> <p>Two (2) dash-mounted cup holders, right-hand and left-hand</p> <p>Gray Vinyl Upholstery</p> <p>Dual Sun visors</p> <p>Fresh Air Heater and Defroster</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
- Gray Vinyl Upholstery		
<b><u>CAB GRILLE, INTERIOR CONVENIENCE AND EXTERIOR APPEARANCE PACKAGE</u></b>		
The cab exterior shall have a high impact plastic chromed grille and matching headlight bezels. The grille shall tilt with the hood.		
Additionally, the headlight bezels and the engine air intake housing shall have a chrome finish.		
The cab interior shall include wood grain dash panels, molded door panels with vinyl inserts and brushed aluminum door kick plates.		
<b><u>MIRRORS</u></b>		
West Coast style heated, remote operated mirrors constructed from a molded composite material with a bright finish shall be provided. A heated 8.00" convex mirror shall be included below the primary mirrors.		
<b><u>CAB ACCESS STEPS</u></b>		
The cab access steps shall be provided by the apparatus manufacturer. The steps shall be a two (2) step design fabricated from bright aluminum tread plate.		
The step assembly shall enclose the area under the cab, including the DEF tank. The fuel and DEF tank fill caps shall be exposed for refueling if located under the cab. Access shall be provided to inspect the chassis batteries when located under the cab.		
<b><u>STEP LIGHTS</u></b>		
There shall white LED step lights provided to meet NFPA step lighting requirements. Lights shall be installed at each cab door step.		
The lights shall be activated when the adjacent door is opened.		
<b><u>DAYTIME RUNNING LIGHTS</u></b>		
The chassis shall be provided with daytime running lights.		
<b><u>AIR CONDITIONING</u></b>		
An air conditioner shall be provided that is integral with heater and defroster system.		
<b><u>ENGINE COMPARTMENT LIGHTS</u></b>		
Two (2) engine compartment lights shall be installed under the engine hood, of which the		
<b><u>SEATING CAPACITY</u></b>		
The seating capacity in the cab shall be two (2).		

	Bidder Complies	
	Yes	No
<p><b><u>SEATING</u></b> Seating inside the cab shall consist of an air-ride driver seat and a fixed companion seat.</p> <p><b><u>SEAT BELT WEB LENGTH</u></b> NFPA 1901, 2016 edition, Section 14.1.3.1 and 14.1.3.2 requires effective seat belt web length for a Type 1 lap belt for pelvic restraint to be a minimum of 60.00", and a Type 2 pelvic and upper torso restraint-style seat belt assembly to be a minimum of 110.00".</p> <p>Per Fire Department specification of a commercial chassis, this apparatus may not have seat belts of the required length. These belts may not provide sufficient length for large firefighters in bunker gear. This apparatus shall be non-compliant to NFPA 1901 standards effective at time of contract execution. This vehicle will have this issue corrected to comply with the NFPA standard prior to delivery of completed apparatus.</p> <p><b><u>SEAT BELTS</u></b> All seating positions in the cab shall have highly visible (orange or bright red) seat belts.</p> <p><b><u>HELMET STORAGE PROVIDED BY APPRATUS MANUFACTURER OR THE DEALER</u></b> NFPA 1901, 2016 edition, section 14.1.7.4.1 requires a location for helmet storage be provided.</p> <p>The fire department and the dealer will agree on an appropriate location for storage of helmets and the apparatus manufacturer or dealer will install them.</p> <p><b><u>PORTABLE HAND LIGHTS, PROVIDED BY FIRE DEPARTMENT</u></b> NFPA 1901, 2016 edition, section 7.9.4 requires two portable hand lights mounted in brackets fastened to the apparatus.</p> <p>The hand lights are not on the apparatus as manufactured. The fire department shall provide and mount these hand lights.</p> <p><b><u>CAB INSTRUMENTS</u></b></p> <ul style="list-style-type: none"> <li>- Engine Temperature Gauge and Warning Buzzer</li> <li>- Engine Oil Pressure Gauge and Warning Buzzer</li> <li>- Speedometer with Odometer</li> <li>- Engine Tachometer</li> <li>- Engine Hour meter</li> <li>- Fuel Level Gauge</li> </ul>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>- DEF Level Gauge and Warning Lamp with 2010+ engines</p> <p>- Voltmeter: Low voltage red warning light and audible alarm</p> <p>- Air Brake Pressure Gauge</p> <p>- Air Restriction Indicator</p> <p>- Circuit Breakers: For overload protection of electric circuits</p> <p>- Ignition Switch: Keyless type</p> <p><b><u>EMERGENCY SWITCH PANEL</u></b></p> <p>An emergency switch panel shall be provided in the cab. The switch panel shall be located within reach of the driver. All NFPA required emergency lights shall be controlled from the master emergency switch. References within this specification to a "switch in the cab" for zone specific options shall mean the emergency master switch.</p> <p><b><u>"DO NOT MOVE APPARATUS" INDICATOR</u></b></p> <p>A flashing red indicator light (located in the driving compartment) shall be illuminated automatically per the current edition of NFPA. The light shall be labeled "Do Not Move Apparatus If Light Is On".</p> <p>The same circuit that activates the Do Not Move Apparatus indicator shall not activate any alarm when the parking brake is released.</p> <p><b><u>DO NOT MOVE TRUCK MESSAGES</u></b></p> <p>A message shall be displayed on the VMUX display in view of the driver whenever any of the following conditions exist:</p> <ul style="list-style-type: none"> <li>• CAB DOOR OPEN (Any Cab Door Open with ignition on)</li> <li>• LH COMPARTMENT OPEN (Any Left Hand Compartment Door Open)</li> <li>• RH COMPARTMENT OPEN (Any Right Hand Compartment Door Open)</li> <li>• REAR DOOR OPEN (Any Rear Compartment Door Open)</li> <li>• TANK RACK DOWN (Tank Rack Not Stowed)</li> <li>• LH LIGHT POLE RAISED (Left Hand Pole Light Raised)</li> <li>• RH LIGHT POLE RAISED (Right Hand Pole Light Raised)</li> </ul> <p>A warning message shall also be displayed for any other device that is opened, extended or deployed that creates a hazard or is likely to cause major damage to the apparatus if the apparatus is moved.</p>		

Bidder Complies	
Yes	No

**WIPER CONTROL**

Wiper control shall include an intermittent feature and windshield washer controls.

**POWER RECEPTACLES**

There shall be two (2) power receptacles located in the dash provided by the chassis manufacturer.

The circuit(s) may be load managed when the parking brake is set.

**VEHICLE DATA RECORDER**

There shall be a vehicle data recorder (VDR) capable of reading and storing vehicle information provided.

The information stored on the VDR can be downloaded through a USB port mounted in a convenient location determined by cab model. A USB cable can be used to connect the VDR to a laptop to retrieve required information. The program to download the information from the VDR will be available to download on-line.

The vehicle data recorder shall be capable of recording the following data via hardwired and/or CAN inputs:

- Vehicle Speed - MPH
- Acceleration - MPH/sec
- Deceleration - MPH/sec
- Engine Speed - RPM
- Engine Throttle Position - % of Full Throttle
- ABS Event - On/Off
- Seat Occupied Status - Yes/No by Position
- Seat Belt Buckled Status - Yes/No by Position
- Master Optical Warning Device Switch - On/Off
- Time - 24 Hour Time
- Date - Year/Month/Day

**Seat Belt Monitoring System**

A seat belt monitoring system (SBMS) shall be provided. The SBMS shall be capable of monitoring all seating positions indicating the status of each seat position per the following:

- Seat Occupied & Buckled = Green LED indicator illuminated
- Seat Occupied & Unbuckled = Red LED indicator with audible alarm
- No Occupant & Buckled = Red LED indicator with audible alarm
- No Occupant & Unbuckled = No indicator and no alarm

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>The SBMS shall include an audible alarm that shall warn that an unbuckled occupant condition exists and the parking brake is released, or the transmission is not in park.</p> <p><b><u>TWO-WAY RADIO ACCOMMODATION PACKAGE</u></b></p> <p>One set of 12 volt wire leads shall be provided for the future installation of a two-way radio. These leads shall consist of one (1) 30-amp battery direct circuit, one (1) 10-amp battery switched circuit and one (1) ground circuit. These leads shall be 6' long and terminate behind the cab dash with heat shrink caps.</p> <p>One (1) NMO mobile radio antenna mount with RG-58A/U stranded coaxial cable shall be provided. The antenna mount shall be installed through the cab roof, and the coaxial cable shall be routed behind the cab dash. All wiring shall be neatly coiled and clearly marked.</p> <p>A weatherproof cap for the antenna mount shall also be installed.</p> <p><b><u>VEHICLE CAMERA SYSTEM</u></b></p> <p>There shall be a color vehicle camera system provided with the following:</p> <ul style="list-style-type: none"> <li>• One (1) camera located at the rear of the apparatus, pointing rearward, displayed automatically with the vehicle in reverse</li> </ul> <p>The camera image shall be displayed on a 7.00" LCD display located in view of the driver on the dash . The display shall include manual camera activation capability and audio from the active camera.</p> <p>The following components shall be included:</p> <ul style="list-style-type: none"> <li>• One (1) MO700136DC Display</li> <li>• One (1) SV-CW134639CAI Camera</li> <li>• All necessary cables</li> </ul> <p><b><u>VEHICLE CAMERA GUARD</u></b></p> <p>There shall be one (1) aluminum tread plate guard provided over the vehicle camera.</p> <p><b><u>ELECTRICAL</u></b></p> <p>All 12-volt electrical equipment installed by the apparatus manufacturer shall conform to modern automotive practices. All wiring shall be high temperature crosslink type. Wiring shall be run in loom or conduit where exposed and have grommets where wire passes through sheet metal. Automatic reset circuit breakers shall be provided which conform to SAE Standards. Wiring shall be color, function and number coded. Function and number codes shall be continuously imprinted on all wiring harness conductors at 2.00" intervals. Exterior exposed wire connectors shall be positive locking, and environmentally sealed to withstand elements such as temperature</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>extremes, moisture and automotive fluids. Electrical wiring and equipment shall be installed utilizing the following guidelines:</p> <p>(1) All holes made in the roof shall be caulked with silicon. Rope caulk is not acceptable. Large fender washers, liberally caulked, shall be used when fastening equipment to the underside of the cab roof.</p> <p>(2) Any electrical component that is installed in an exposed area shall be mounted in a manner that shall not allow moisture to accumulate in it. Exposed area shall be defined as any location outside of the cab or body.</p> <p>(3) Electrical components designed to be removed for maintenance shall not be fastened with nuts and bolts. Metal screws shall be used in mounting these devices. Also a coil of wire shall be provided behind the appliance to allow them to be pulled away from mounting area for inspection and service work.</p> <p>(4) Corrosion preventative compound shall be applied to all terminal plugs located outside of the cab or body. All non-waterproof connections shall require this compound in the plug to prevent corrosion and for easy separation (of the plug).</p> <p>(5) All lights that have their sockets in a weather exposed area shall have corrosion preventative compound added to the socket terminal area.</p> <p>(6) All electrical terminals in exposed areas shall have silicon (1890) applied completely over the metal portion of the terminal. All emergency light switches shall be mounted on a separate panel installed in the cab. A master warning light switch and individual switches to be provided to allow pre-selection of emergency lights. The light switches shall be "rocker" type with an internal indicator light to show when switch is energized. All switches shall be properly identified and mounted in a removable panel for ease in servicing. Identification of the switches shall be done by either printing or etching on the switch panel. The switches and identification shall be illuminated.</p> <p>All lights and reflectors, required to comply with Federal Motor Vehicle Safety Standard #108, shall be furnished. Rear identification lights shall be recessed mounted for protection. Lights and wiring mounted in the rear bulkheads shall be protected from damage by installing a false bulkhead inside the rear compartments.</p> <p>An operational test shall be conducted to ensure that any equipment that is permanently attached to the electrical system is properly connected and in working order.</p> <p>The results of the tests shall be recorded and provided to the purchaser at time of delivery.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

Bidder Complies	
Yes	No

**BATTERY SYSTEM**

A single starting battery system shall be provided consisting of two (2) 12 volt, 1125 CCA, maintenance-free, group 31 batteries. The battery system shall have a total of 2250 CCA.

**Jump Start Connections**

Positive and negative posts for jump starting shall be provided by the chassis manufacturer. They shall be frame mounted and located under the hood.

**MASTER BATTERY SWITCH**

A master battery switch, to activate the battery system, shall be provided inside the cab within easy reach of the driver.

The master battery disconnect switch shall be wired between the starter solenoid and the remainder of the electrical loads on the apparatus.

A green "battery on" indicator light, visible from the driver's position, shall be provided.

**BATTERY CHARGER/ AIR COMPRESSOR**

A Kussmaul Pump Plus 1000, Model 51-21-1100, 15 amp single output battery charger/air compressor system with internal battery saver shall be provided. A display bar graph indicating the state of charge shall be included.

The battery saver circuit shall be capable of supplying up to three (3) additional amps for external loads such as hand lights or auxiliary radio batteries.

The 12-volt air compressor shall be installed to maintain the air system pressure when the vehicle is not in use.

The battery charger shall be wired to the AC shoreline inlet through an AC receptacle adjacent to this battery charger.

**BATTERY CHARGER LOCATION**

The battery charger shall be located in the left side forward body compartment. It shall be mounted as high and forward as practical to keep it protected and away from other equipment in the compartment.

The battery charger indicator shall be located on the driver's side pump panel.

**KUSSMAUL AUTO EJECT FOR SHORELINE**

One (1) shoreline inlet shall be provided to operate the dedicated 120-volt circuits on the truck without the use of the generator.

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>The shoreline receptacle (s) shall be provided with a NEMA 5-20, 120 volt, 20 amp, straight blade Kussmaul auto eject plug with a yellow weatherproof cover. The cover is spring loaded to close, preventing water from entering when the shoreline is not connected.</p> <p>A solenoid wired to the vehicle's starter is energized when the engine is started. This instantaneously drives the plug from the receptacle.</p> <p>The shoreline shall be connected to the battery charger.</p> <p>A mating connector body shall also be supplied with the loose equipment.</p> <p>The shoreline receptacle shall be located at the driver's side, rear of vehicle.</p> <p><b><u>ALTERNATOR</u></b></p> <p>The alternator shall be a Delco Remy 40SI, 275 amp, quadramount, with remote battery voltage sensor.</p> <p><b><u>ELECTRONIC LOAD MANAGEMENT</u></b></p> <p>Included with the apparatus manufacturer's electrical system shall be a programmable load management system.</p> <p>This system shall monitor the vehicle's 12-volt electrical system, and automatically reduce the electrical load in the event of a low voltage condition and by doing so, ensures the integrity of the electrical system.</p> <p><b><u>EXTERIOR LIGHTING</u></b></p> <p>Exterior lighting shall meet or exceed Federal Department of Transportation, Federal Motor Vehicle Safety Standards and National Fire Protection Association requirements in effect at time of proposal.</p> <p>Front headlights shall be halogen type and comply to all FMVSS requirements.</p> <p>Five (5) LED clearance and marker lights shall be installed across the leading edge of the cab.</p> <p><b><u>INTERMEDIATE LIGHT</u></b></p> <p>There shall be two (2) Truck-Lite®, Model 60115Y, amber LED lights furnished, one (1) each side, horizontally in the rear fender panel. The light shall double as a turn signal and marker light.</p> <p>A stainless steel trim shall be included with this installation.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

Bidder Complies	
Yes	No

**REAR CLEARANCE/MARKER/ID LIGHTING**

There shall be a three (3) LED light bar used as identification lights located at the rear of the apparatus per the following:

- As close as practical to the vertical centerline
- Centers spaced not less than 6.00" or more than 12.00" apart
- Red in color
- All at the same height

There shall be two (2) Truck-Lite®, Model 33050R, LED lights installed at the rear of the apparatus used as clearance lights located at the rear of the apparatus per the following:

- To indicate the overall width of the vehicle
- One (1) each side of the vertical centerline
- As near the top as practical
- Red in color
- To be visible from the rear
- All at the same height

There shall be two (2) Truck-Lite, Model 33050R, LED lights installed on the side of the apparatus used as marker lights located as close to the rear as practical per the following:

- To indicate the overall length of the vehicle
- One (1) each side of the vertical centerline
- As near the top as practical
- Red in color
- To be visible from the side
- All at the same height

Two (2) red reflectors located on the rear of the truck facing to the rear. One (1) each side, as far to the outside as practical, at a minimum of 15.00", but no more than 60.00", above the ground.

Two (2) red reflectors located on the side of the truck facing to the side. One (1) each side, as far to the rear as practical, at a minimum of 15.00", but no more than 60.00", above the ground.

Per FMVSS 108 and CMVSS 108 requirements.

**REAR FMVSS LIGHTING**

There shall be the following stop/tail and directional lighting provided at the rear of the truck:

- Two (2) Whelen®, Model 60BTT, red LED stop/tail lights with clear lenses

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<ul style="list-style-type: none"> <li>Two (2) Whelen, Model 60A00TAR, amber LED directional lights</li> </ul> <p>The lights shall be mounted in a polished combination housing.</p> <p>Two (2) Whelen Model 60C00VCR, LED backup lights shall be provided.</p> <p><b><u>LIGHTING BEZEL</u></b></p> <p>Two (2) Whelen, Model PLAST4V, four (4) light chrome plated composite plastic housings shall be provided for the rear stop/tail, directional, scene lights and warning.</p> <p><b><u>BACK-UP ALARM</u></b></p> <p>A PRECO, Model 1040, solid-state electronic audible back-up alarm that actuates when the truck is shifted into reverse shall be provided. The device shall sound at 60 pulses per minute and automatically adjust its volume to maintain a minimum ten (10) dBA above surrounding environmental noise levels.</p> <p><b><u>CAB PERIMETER SCENE LIGHTS</u></b></p> <p>There shall be two (2) Truck-Lite, Model 6060C, white LED lights with grommets provided, one (1) for each cab door.</p> <p>These lights shall be activated automatically when the battery switch is on and the exit doors are opened or by the same means as the body perimeter scene lights.</p> <p><b><u>PUMP HOUSE PERIMETER LIGHTS</u></b></p> <p>There shall be two (2) Truck-Lite, Model 6060C, white LED lights with grommets provided under the pump panel running boards, one (1) each side.</p> <p>The lights shall be controlled by the same means as the body perimeter lights.</p> <p><b><u>BODY PERIMETER SCENE LIGHTS</u></b></p> <p>There shall be two (2) Truck-Lite, Model 6060C, white LED lights with grommets provided under at the rear step area of the body, one (1) each side shining to the rear.</p> <p>The perimeter scene lights shall be activated when the parking brake is applied.</p> <p><b><u>STEP LIGHTS</u></b></p> <p>White LED, step lights shall be provided to meet the NFPA step lighting requirement. Lights shall be provided on each side, on the front compartment face and at the rear to illuminate the tailboard.</p> <p>These step lights shall be actuated with the parking brake.</p> <p>All other steps on the apparatus shall be illuminated per the current edition of NFPA 1901.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>SCENE LIGHTS</u></b></p> <p>There shall be one (1) pair of Whelen, Model 6SC0ENZR Gradient LED scene lights provided. These lights shall direct light downward via internal optics. There shall be one (1) light each side on the rear of the apparatus. These lights shall be installed no higher than 72.00" above the ground.</p> <p>A control for the lights selected above shall be the following:</p> <ul style="list-style-type: none"> <li>• a switch at the driver's side switch panel</li> <li>• a switch at the interior emergency switch panel</li> </ul> <p><b><u>SCENE LIGHTS</u></b></p> <p>There shall be one (1) pair of Whelen, Model 6SC0ENZR Gradient LED scene lights provided. These lights shall direct light downward via internal optics. There shall be one (1) pair installed on the driver's side of the apparatus body.</p> <p>A control for the lights selected above shall be the following:</p> <ul style="list-style-type: none"> <li>• a switch at the driver's side pump panel</li> <li>• a switch at the interior emergency switch panel</li> </ul> <p><b><u>SCENE LIGHTS</u></b></p> <p>There shall be one (1) pair of Whelen, Model 6SC0ENZR Gradient LED scene lights provided. These lights shall direct light downward via internal optics. There shall be one (1) pair installed on the passenger's side of the apparatus body.</p> <p>A control for the lights selected above shall be the following:</p> <ul style="list-style-type: none"> <li>• a switch at the driver's side pump panel</li> <li>• a switch at the interior emergency switch panel</li> </ul> <p><b><u>WATER TANK</u></b></p> <p>The tank shall have a minimum capacity of 3000 U.S. gallons. The tank shall be of a specified configuration and designed to be completely independent of the compartment and/or fender modules. When placed on the chassis, the tank shall meet or exceed all federal DOT regulations regarding weight distribution, axle loading and horizontal and vertical center of gravity locations. The tank manufacturer shall mark the tank with the manufacturer's name, date of manufacture, and serial number. The tank manufacturer shall furnish notice that indicates proof of warranty.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>The tank shall be constructed using a virgin polypropylene sheet with a minimum thickness of .50". This material shall be a high impact copolymer (HIC), non-corrosive, stress relieved thermoplastic, UV stabilized for maximum protection.</p> <p>All joints and seams shall be nitrogen welded and tested for maximum strength and integrity. All swash partitions shall interlock and be welded to each other as well as to the walls of the tank.</p> <p>The tank shall incorporate a manual fill tower with a 6.00" combination vent/overflow pipe. The fill tower shall be constructed of polypropylene and shall be large enough to provide filling by means of a conventional 2.50" hose nozzle. The tower shall be located near the center of the tank to minimize water surge during vehicle operation. The tower shall have a removable polypropylene screen and a polypropylene hinged cover. The vent/overflow pipe shall run through the tank and exit through the floor of the tank behind the rear axle.</p> <p>The sides of the tank shall be painted to match the remainder of the unit.</p> <p>The tank and hose bed (if provided) shall be removable as a unit and shall be a separate component from the body compartmentation.</p> <p><b><u>WATER TANK RESTRAINT</u></b></p> <p>A heavy-duty water tank restraint shall be provided to keep the water tank in position. This requirement is especially critical when the tank is empty and the apparatus is traveling over rough terrain.</p> <p><b><u>TOP OF TANK, ACCESS LADDER</u></b></p> <p>An access ladder constructed of aluminum tubing shall be provided for access to the hose bed and/or tank dome. The ladder shall have a flexible mount attached to the tailboard. The ladder shall be located on the passenger side, rear of the vehicle.</p> <p><b><u>TANK OVERFLOW/VENT</u></b></p> <p>A tube shall be installed through the shell of the tank. This tube shall function as an overflow to discharge water to the ground once the tank is filled to capacity. It shall be sized large enough to accommodate filling the tank with a 5.00" hose at 70 PSI without causing damage to the tank. A letter from the tank manufacturer is required to be given to the department stating that the tank is designed to handle such filling conditions and that the warranty on the tank is not jeopardized by such actions. It shall also function as a vent to allow air to enter the tank when water is being dumped or pumped from the tank.</p> <p>The tube shall be positioned to drain at the bottom of the truck near the center, behind the rear axle.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>FOLD-A-TANK RACKS</u></b></p> <p>A quantity of one (1) Zico Quic-Lift PTS-HA hydraulic rack(s) shall be provided on passenger's side for storage of a 3000 gallon aluminum framed Fold-a-Tank (w/closed dimensions of 159" x 9" x 30") portable folding tank. The Quic-Lift lowering system shall be powered by two (2) self-contained hydraulic actuators.</p> <p>The controls shall be located in such a manner to allow the operator full view of the area in which the fold-a-tank shall be lowered.</p> <p>The actuator control shall have a master switch and also be interlocked to prevent operation should a compartment door, in the travel area of the rack, be in the open position.</p> <p>An aluminum cover, painted the same color as the body of the apparatus, shall be installed on the lowering device to protect and conceal the fold-a-tank when in the stored position. This cover shall be installed with a Zico mounting kit to allow for flexing.</p> <p><b><u>RACK INTERLOCK AND NOT STOWED INDICATOR LIGHT</u></b></p> <p>An interlock shall be provided to prevent operation of the rack unless the apparatus parking brake has been activated.</p> <p>A steady amber indicator light shall be located on the cab instrument panel and illuminated when the rack is not in the stowed position. The light shall be labeled "TANK RACK DOWN". In addition, the "Do Not Move Apparatus" light located in the cab shall be activated when the rack is not in the stowed position.</p> <p><b><u>LIGHTS, FLASHING, RACK</u></b></p> <p>Flashing amber lights facing the front and rear shall be provided on the rack and activated whenever the rack is in the down position.</p> <p><b><u>REAR TANK FILL</u></b></p> <p>A 4.00" gated external tank fill shall be installed and properly labeled at the rear of the water tank, located driver's side of the tank.</p> <p>Piping, for the fill, shall be routed through the rear wall of the tank and include a flow deflector to break up the stream of water entering the water tank.</p> <p>A 4.00" (M)NST x 5.00" Storz hard coat aluminum 30 degree elbow adapter and 5.00" blind cap shall be provided for the tank fill.</p> <p><b><u>REAR TANK DUMP VALVE</u></b></p> <p>One (1) 10.00" Newton Quick Dump shall be installed at the rear of the tank. The valve shall be operated manually by a lever control located on top of the valve.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>A 180 degree, Newton 6012SW swivel dump chute shall be provided.</p> <p>The chute shall include a Newton 4036 telescopic extension to allow the chute to extend past the body side for dumping.</p> <p>The water tank design shall include additional support for this chute.</p> <p><b><u>RUNNING BOARDS</u></b></p> <p>Running boards shall be fabricated of .125" bright aluminum tread plate.</p> <p>Each running board shall be supported by a welded 2.00" square tubing and channel assembly, which shall be bolted to the pump compartment substructure.</p> <p>Running boards shall be 12.75" deep and spaced .50" away from the pump panel.</p> <p>A splash guard shall be provided above the running board tread plate.</p> <p><b><u>TAILBOARD</u></b></p> <p>A tailboard approximately 16.00" deep and covered with bright aluminum tread plate shall be provided at the rear of the truck.</p> <p><b><u>TOW EYES</u></b></p> <p>Two (2) rear painted tow eyes shall be located at the rear of the apparatus and shall be mounted directly to the chassis frame rails. The inner and outer edges of the tow eyes shall have a radius.</p> <p><b><u>COMPARTMENTATION</u></b></p> <p>Body and compartments shall be fabricated of .125", 5052-H32 aluminum.</p> <p>Side compartments shall be an integral assembly with the rear fenders.</p> <p>Circular fender liners shall be provided for prevention of rust pockets and ease of maintenance.</p> <p>Compartment flooring shall be of the sweep out design with the floor higher than the compartment door lip.</p> <p>Drip protection shall be provided above the doors.</p> <p>All screws and bolts which protrude into a compartment shall have acorn nuts on the ends to prevent injury.</p> <p><b><u>BODY SUPPORT SYSTEM</u></b></p> <p>Due to the loading requirements of this tanker, a method of body and compartment support suitable for the intended load shall be provided.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>The backbone of the support system shall be the chassis frame rails which is the strongest component of the chassis and is designed for sustaining maximum loads.</p> <p><b><u>AGGRESSIVE WALKING SURFACE</u></b>                      All exterior surfaces designated as stepping, standing, and walking areas shall comply with the required average slip resistance of the current NFPA standards.</p> <p><b><u>COMPARTMENTATION, DRIVER'S SIDE</u></b>                      A roll-up door compartment in the lower area, ahead of the rear wheels shall be provided. The interior dimensions shall be 54.00" wide x 27.00" high x 24.50" deep. The depth of the compartment shall be calculated with the compartment door closed. The clear door opening of the compartment shall be 51.75" wide x 32.00" high. Closing of the door shall not require releasing, unlocking, or unlatching any mechanism and shall easily be accomplished with one hand.</p> <p>A roll-up door compartment in the lower area, behind the rear wheels shall be provided. The interior dimensions of this compartment shall be 22.00" wide x 27.75" high x 24.50" deep. The depth of the compartment shall be calculated with the compartment door closed. The clear door opening of this compartment shall be 19.75" wide x 22.50" high. Closing of the door shall not require releasing, unlocking, or unlatching any mechanism and shall easily be accomplished with one hand.</p> <p><b><u>HARD SUCTION HOSE COMPARTMENT WITH PIKE POLE STORAGE</u></b>                      A hard suction hose storage compartment shall be provided as an integral part of the driver's side body compartments. The hose storage compartment shall be fabricated of the same material as the body compartment and shall be fully enclosed. Access to the hose shall be through a vertically hinged aluminum tread plate steel door at the rear. The compartment shall accommodate a 5" hard suction hose and a 12 foot pike pole.</p> <p><b><u>COMPARTMENTATION, PASSENGER'S SIDE</u></b>                      A roll-up door compartment in the lower area, ahead of the rear wheels shall be provided. The interior dimensions shall be 54.00" wide x 27.00" high x 24.50" deep. The depth of the compartment shall be calculated with the compartment door closed. The clear door opening of the compartment shall be 51.75" wide x 32.00" high. Closing of the door shall not require releasing, unlocking, or unlatching any mechanism and shall easily be accomplished with one hand.</p> <p>A roll-up door compartment in the lower area, behind the rear wheels shall be provided. The interior dimensions of this compartment shall be 22.00" wide x 27.75" high x 24.50" deep. The depth of the compartment shall be calculated with the compartment door closed. The clear door opening of this compartment shall be 19.75" wide x 22.50" high. Closing of the door shall not</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>require releasing, unlocking, or unlatching any mechanism and shall easily be accomplished with one hand.</p> <p><b><u>HARD SUCTION HOSE COMPARTMENT WITH PIKE POLE STORAGE</u></b></p> <p>A hard suction hose storage compartment shall be provided as an integral part of the passenger's side body compartments. The hose storage compartment shall be fabricated of the same material as the body compartment and shall be fully enclosed. Access to the hose shall be through a vertically hinged tread plate door at the rear. The compartment shall accommodate a 5" hard suction hose and a 12 foot pike pole.</p> <p><b><u>ROLL-UP DOOR, SIDE COMPARTMENTS</u></b></p> <p>There shall be four (4) compartment doors installed on the side compartments. The doors shall be double faced aluminum construction, an anodized satin finish.</p> <p>Lath sections shall be an interlocking rib design and shall be individually replaceable without complete disassembly of door.</p> <p>Between each slat at the pivoting joint shall be a PVC inner seal to prevent metal to metal contact and prevent dirt or moisture from entering the compartments. Seals shall allow door to operate in extreme temperatures ranging from plus 180 to minus 40 degrees Fahrenheit. Side, top and bottom seals shall be provided to resist ingress of dirt and weather.</p> <p>All hinges, barrel clips and end pieces shall be nylon 66. All nylon components shall withstand temperatures from plus 300 to minus 40 degrees Fahrenheit. Hardened plastic shall not be acceptable.</p> <p>A polished stainless steel lift bar to be provided for each roll-up door. Lift bar shall be located at the bottom of door and have latches on the outer extrusion of the doors frame. A ledge shall be supplied over lift bar for additional area to aid in closing the door.</p> <p>Doors shall be constructed from an aluminum box section. The exterior surface of each slat shall be flat. The interior surfaces shall be concave to provide strength and prevent loose equipment from jamming the door from inside.</p> <p>To conserve space in the compartments, the spring roller assembly shall not exceed 3.00" in diameter. A garage style roll door shall not be acceptable.</p> <p>The header for the roll-up door assembly shall not exceed 4.00".</p> <p>A heavy-duty magnetic switch shall be used for control of open compartment door warning lights.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>COMPARTMENT LIGHTING</u></b></p> <p>There shall be four (4) compartments with LED compartment light strips. There shall be three (3) pairs of lights required - one pair in each forward compartment and a single light in each rear compartment.</p> <p>Each strip shall be centered vertically along the door framing. All body compartments with roll-up doors shall have these strip lights.</p> <p>Any remaining compartments shall include 6.00" diameter Truck-Lite, Model: 79384 light in each enclosed compartment. Each light shall have a number 1076 one filament, two wire bulb.</p> <p>Opening the compartment door shall automatically turn the compartment lighting on.</p> <p><b><u>MOUNTING TRACKS</u></b></p> <p>There shall be four (4) sets of tracks for mounting shelf(s) in each body compartment. These tracks shall be installed vertically to support the adjustable shelf(s), and shall be full height of the compartment. The tracks shall be unpainted with a natural finish.</p> <p><b><u>ADJUSTABLE SHELVES</u></b></p> <p>There shall be two (2) shelves with a capacity of 215 lb provided. The shelf construction shall consist of .18" aluminum with 2.00" sides. Each shelf shall be painted to match the compartment interior. Each shelf shall be infinitely adjustable by means of a threaded fastener, which slides in a track.</p> <p>The shelves shall be held in place by .12" thick stamped plated brackets and bolts.</p> <p>The location shall be determined later.</p> <p><b><u>BODY FENDER CROWNS</u></b></p> <p>Stainless steel fender crowns shall be provided around the rear wheel openings.</p> <p>A rubber welting shall be provided between the body and the crown to seal the seam and restrict moisture from entering.</p> <p><b><u>HARD SUCTION HOSE</u></b></p> <p>Hard suction hose shall not be required.</p> <p><b><u>AIR BOTTLE STORAGE (DOUBLE)</u></b></p> <p>A quantity of two (2) air bottle compartments, 15.25" wide x 7.75" tall x 26.00" deep, constructed from stainless steel shall be provided. There shall be one (1) compartment located on each side of the body between the tandem axles.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>A polished stainless steel door with a chrome plated flush lift &amp; turn latch shall be provided to contain the air bottle. A dielectric barrier shall be provided between the door hinge, hinge</p> <p><b><u>FIRE PUMP</u></b></p> <p>Fire pump shall be a Hale MBP100, 1000 gpm, single stage, mid-ship mounted, centrifugal type.</p> <p>Pump shall be the class "A" type.</p> <p>Pump shall deliver the percentage of rated discharges at the pressures indicated below:</p> <ul style="list-style-type: none"> <li>- 100% of rated capacity at 150 psi net pump pressure.</li> <li>- 100% of rated capacity at 165 psi net pump pressure.</li> <li>-70% of rated capacity at 200 psi net pump pressure.</li> <li>-50% of rated capacity at 250 psi net pump pressure.</li> </ul> <p>Entire pump, both suction and discharge passages, shall be hydrostatically tested to a pressure of 600 psi (40.8 bar).</p> <p>Pump shall be fully tested at the pump manufacturer's factory to the performance requirements as outlined by the latest NFPA pamphlet #1901, and shall be free from objectionable pulsation and vibration.</p> <p>The pump body and related parts shall be of fine grain alloy cast iron, with a minimum tensile strength of 30,000 psi (2041.2 bar). All moving parts in contact with water shall be of high quality bronze or stainless steel. Pumps utilizing castings made of lower tensile strength cast iron not acceptable.</p> <p>Pump body shall be vertically split, on a single plane.</p> <p>Pump impeller shall be hard, fine grain bronze of the mixed flow design, accurately machined, hand-ground, and individually balanced. The vanes of the impeller intake eyes shall be hand-ground and polished to a sharp edge, and be of sufficient size and design to provide ample reserve capacity utilizing minimum horsepower.</p> <p>Impeller clearance rings shall be bronze, easily renewable without replacing impeller or pump volute body.</p> <p>Pump shaft shall be electric furnace, heat-treated, corrosion resistant stainless steel. Pump shaft must be sealed with double oil seal to keep road dirt and water out of drive unit.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>MECHANICAL SEAL ON PUMP</u></b></p> <p>Only one (1) mechanical seal shall be required on the suction (inboard) side of the pump. The mechanical seal shall be two (2.00) inches in diameter and shall be spring loaded, maintenance-free, and self-adjusting.</p> <p>The mechanical seal construction shall be a carbon sealing ring, stainless steel coil spring, Viton® rubber boot, and a tungsten carbide seat with a Teflon backup seal.</p> <p><b><u>PUMP TRANSMISSION</u></b></p> <p>Pump transmission shall be tested at the pump manufacturer's factory. The gearbox drive shaft shall be heated treated chromium steel. All gears shall be high quality electric furnace chrome nickel steel.</p> <p>Drive shafts shall be a minimum of 1.50" diameter hardened and ground alloy steel. All shafts shall be ball bearing supported.</p> <p>The water pump shall be driven by a hot shift PTO shall be located on the chassis transmission.</p> <p><b><u>PUMPING MODE</u></b></p> <p>An interlock system shall be provided to ensure that the pump drive system components are properly engaged so that the apparatus can be safely operated. Interlock system shall be designed to allow the truck to be in motion while pumping.</p> <p><b><u>PUMP SHIFT</u></b></p> <p>A pump shift shall be provided within easy reach of the driver for engagement of the PTO driven pump. The shift shall include the indicator lights as mandated by NFPA. The pump shift control shall be illuminated to meet NFPA requirements.</p> <p><b><u>AUXILIARY COOLING SYSTEM</u></b></p> <p>A supplementary heat exchange cooling system shall be provided to allow the use of water from the discharge side of the pump for cooling the engine water. Heat exchanger shall be cylindrical type and shall be a separate unit. It shall be installed in the pump or engine compartment with the control located on the pump operator's control panel. Exchanger shall be plumbed to the master drain valve.</p> <p><b><u>INTAKE RELIEF VALVE</u></b></p> <p>An intake relief valve shall be installed on the suction side of the pump preset at 125 psig.</p> <p>Relief valve shall have a working range of 50 psig to 350 psig.</p> <p>Outlet shall terminate below the frame rails with a 2.50" National Standard hose thread adapter and shall have a "do not cap" warning tag.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

Bidder Complies	
Yes	No

**PRESSURE CONTROLLER**

A Fire Research Pump Boss Model PBA200 pressure governor shall be provided.

A pressure transducer shall be installed in the water discharge manifold on the pump.

The display panel shall be located at the pump operator's panel.

**PRIMING PUMP**

The priming pump shall be a Trident Emergency Products compressed air powered, high efficiency, multistage venturi based AirPrime System, conforming to standards outlined in the current edition of NFPA 1901.

All wetted metallic parts of the priming system are to be of brass and stainless steel construction.

One (1) priming control shall open the priming valve and start the pump primer.

**PUMP MANUALS**

There shall be a total of two (2) pump manuals provided by the pump manufacturer and furnished with the apparatus. The manuals shall be provided by the pump manufacturer in the form of two (2) CDs. Each manual shall cover pump operation, maintenance, and parts.

**PLUMBING, STAINLESS STEEL AND HOSE**

All inlet and outlet lines shall be plumbed with either stainless steel pipe, flexible polypropylene tubing or synthetic rubber hose reinforced with hi-tensile polyester braid. All hose's shall be equipped with brass or stainless steel couplings. All stainless steel hard plumbing shall be a minimum of a schedule 10 wall thickness.

Where vibration or chassis flexing may damage or loosen piping or where a coupling is required for servicing, the piping shall be equipped with Victaulic or rubber couplings.

Plumbing manifold bodies shall be ductile cast iron or stainless steel.

All piping lines are to be drained through a master drain valve or shall be equipped with individual drain valves. All drain lines shall be extended with a hose to drain below the chassis frame.

All water carrying gauge lines shall be of flexible polypropylene tubing.

All piping, hose and fittings shall have a minimum of a 500 PSI hydrodynamic pressure rating.

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>MAIN PUMP INLETS</u></b>                      A 6.00" pump manifold inlet shall be provided on each side of the vehicle. The suction inlets shall include removable die cast zinc screens that are designed to provide cathodic protection for the pump, thus reducing corrosion in the pump.</p> <p><b><u>MAIN PUMP INLET CAP</u></b>                      The main pump inlets shall have National Standard Threads with a rocker lug chrome plated cap.</p> <p>The cap shall incorporate a thread design to automatically relieve stored pressure in the line when disconnected (no exception).</p> <p><b><u>VALVES</u></b>                      All ball valves shall be Akron® Brass in-line valves. The Akron valves shall be the 8000 series heavy-duty style with a stainless steel ball and a simple two-seat design. No lubrication or regular maintenance is required on the valve.</p> <p>Valves shall have a <b>ten (10) year</b> warranty.</p> <p><b><u>LEFT SIDE INLET</u></b>                      There shall be one (1) auxiliary inlet with a 2.50" valve at the left side pump panel, terminating with a 2.50" (F) National Standard hose thread adapter.</p> <p>The auxiliary inlet shall be provided with a strainer, chrome swivel and plug.</p> <p>Inlet valve location shall be outside of the pump panel.</p> <p><b><u>INLET CONTROL</u></b>                      The side auxiliary inlet(s) shall incorporate a quarter-turn ball valve with the control located at the inlet valve. The valve operating mechanism shall indicate the position of the valve.</p> <p><b><u>INLET BLEEDER VALVE</u></b>                      A 0.75" bleeder valve shall be provided for each side gated inlet. The valves shall be located behind the panel with a swing style handle control extended to the outside of the panel. The handles shall be chrome plated and provide a visual indication of valve position. The swing handle shall provide an ergonomic position for operating the valve without twisting the wrist and provides excellent leverage. The water discharged by the bleeders shall be routed below the chassis frame rails.</p> <p><b><u>TANK TO PUMP</u></b>                      The booster tank shall be connected to the intake side of the pump with heavy duty 4.00" piping and a quarter turn 3.00" valve with the control remotely located at the operator's panel. A rubber coupling shall be included in this line to prevent damage from vibration or chassis flexing.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>A check valve shall be provided in the tank to pump supply line to prevent the possibility of "back filling" the water tank.</p> <p><b><u>TANK REFILL</u></b>                      A 2.00" combination tank refill and pump bypass line shall be provided using a quarter-turn full flow ball valve, controlled from the pump operator's panel.</p> <p><b><u>LEFT SIDE DISCHARGE OUTLETS</u></b>                      There shall be one (1) discharge outlet with a 2.50" valve on the left side of the apparatus, terminating with a 2.50" (M) National Standard hose thread adapter.</p> <p><b><u>RIGHT SIDE DISCHARGE OUTLETS</u></b>                      There shall be one (1) discharge outlet 2.50" valve on the right side of the apparatus, terminating with a (M) 2.50" National Standard hose thread adapter.</p> <p>There shall be one (1) discharge outlet with a 3.00" valve on the right side of the apparatus, terminating with a (M) 4.00" National Standard hose thread adapter. The outlet shall be controlled by a slow-close valve located at the operator's panel.</p> <p><b><u>DISCHARGE CAPS</u></b>                      Chrome plated, rocker lug, caps with chains shall be furnished for all side discharge outlets.</p> <p>The caps shall incorporate a thread design to automatically relieve stored pressure in the line when disconnected (no exception).</p> <p><b><u>OUTLET BLEEDER VALVE</u></b>                      A 0.75" bleeder valve shall be provided for each outlet 1.50" or larger. Automatic drain valves are acceptable with some outlets if deemed appropriate with the application.</p> <p>The valves shall be located behind the panel with a swing style handle control extended to the outside of the side pump panel. The handles shall be chrome plated and provide a visual indication of valve position. The swing handle shall provide an ergonomic position for operating the valve without twisting the wrist and provides excellent leverage. Bleeders shall be located at the bottom of the pump panel. They shall be properly labeled identifying the discharge they are plumbed in to. The water discharged by the bleeders shall be routed below the chassis frame rails.</p> <p><b><u>LEFT SIDE OUTLET ELBOWS</u></b>                      The 2.50" discharge outlets located on the left side pump panel shall be furnished with a 2.50" (F) National Standard hose thread x 2.50" (M) National Standard hose thread, chrome plated, 45 degree elbow.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>The elbow shall incorporate a thread design to automatically relieve stored pressure in the line when disconnected (no exception).</p> <p><b><u>RIGHT SIDE OUTLET ELBOWS</u></b></p> <p>The 2.50" discharge outlets located on the right side pump panel shall be furnished with a 2.50" (F) National Standard hose thread x 2.50" (M) National Standard hose thread, chrome plated, 45 degree elbow.</p> <p>The elbow shall incorporate a thread design to automatically relieve stored pressure in the line when disconnected (no exception).</p> <p><b><u>ADDITIONAL RIGHT SIDE OUTLET ELBOWS</u></b></p> <p>The 4.00" discharge outlets, located on the right side pump panel, shall be furnished with a 4.00" (F) National Standard hose thread x 5.00" Storz 30 degree elbow and 5" Blind Cap.</p> <p><b><u>DISCHARGE OUTLET CONTROLS</u></b></p> <p>The discharge outlets shall incorporate a quarter-turn ball valve with the control located at the pump operator's panel. The valve operating mechanism shall indicate the position of the valve.</p> <p>If a hand wheel control valve is used, the control shall be a minimum of a 3.9" diameter stainless steel hand wheel with a dial position indicator built in to the center of the hand wheel.</p> <p><b><u>DEADLAY HOSE BED</u></b></p> <p>One (1) hose bed, without plumbing shall be provided above the pump area. It shall have a minimum capacity of 200' of 2.50" double jacketed hose with separation from the other hose lays.</p> <p>Dead lay bed flooring shall consist of removable perforated brushed aluminum.</p> <p><b><u>CROSSLAY HOSE BEDS</u></b></p> <p>Two (2) cross lays with 1.50" outlets shall be provided. Each bed to be capable of carrying 200 feet of 1.75" double jacketed hose and shall be plumbed with 2.00" id. pipe and gated with a 2.00" quarter turn ball valve.</p> <p>Outlets to be equipped with a 1.50" National Standard hose thread 90 degree swivel located in the hose bed so that hose may be removed from either side of apparatus.</p> <p>The cross lay controls shall be at the pump operator's panel.</p> <p>The center cross lay dividers shall be fabricated of .25" aluminum and shall provide adjustment from side to side. The divider shall be unpainted with a DA finish.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>Vertical scuff plates, constructed of stainless steel, shall be provided at the rear ends of the bed on each side of vehicle.</p> <p>Cross lay bed flooring shall consist of removable perforated brushed aluminum.</p> <p><b><u>HOSE BED COVER</u></b></p> <p>A hose bed cover, constructed of .125” bright aluminum tread plate will be furnished. The cover will be hinged with a full length stainless steel piano hinge. The sides will be slanted down.</p> <p>The cover will be reinforced so that it can support the weight of a man walking on the cover.</p> <p>The cover, when open, will activate the “DO NOT MOVE” light inside the cab.</p> <p><b><u>CROSSLAY/DEADLAY HOSE RESTRAINT</u></b></p> <p>There will be a red vinyl flap installed at the end of the hose bed. The flap will be attached to the hose bed cover. The flap will have straps that loop through footman loops at the bottom of the hose bed and fasten with 2.00” release fasteners and not weighted.</p> <p><b><u>PUMP COMPARTMENT</u></b></p> <p>The pump compartment shall be separate from the hose body and compartments so that each may flex independently of the other. It shall be a fabricated assembly of steel tubing, angles and channels which supports both the fire pump and the side running boards.</p> <p>The pump compartment shall be mounted on the chassis frame rails with rubber biscuits in a four point pattern to allow for chassis frame twist.</p> <p>Pump compartment, pump, plumbing and gauge panels shall be removable from the chassis in a single assembly.</p> <p><b><u>PUMP MOUNTING</u></b></p> <p>Pump shall be mounted to a substructure which shall be mounted to the chassis frame rail using rubber isolators. The mounting shall allow chassis frame rails to flex independently without damage to the fire pump.</p> <p><b><u>PUMP CONTROL PANELS (SIDE CONTROL)</u></b></p> <p>All pump controls and gauges shall be located at the left (driver's) side of the apparatus and properly marked.</p> <p>The pump panel on the right (passenger's) side shall be removable with lift and turn type fasteners. The left (driver's) side shall be fastened with screws.</p> <p>The control panels shall be 28.00" wide.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>The gauge and control panels shall be two (2) separate panels for ease of maintenance.</p> <p>Polished stainless steel trim collars shall be installed around all inlets and outlets.</p> <p>All push/pull valve controls shall have 1/4 turn locking control rods with polished chrome plated zinc tee handles. Guides for the push/pull control rods shall be chrome plated zinc castings securely mounted to the pump panel. Push/pull valve controls shall be capable of locking in any position. The control rods shall pull straight out of the panel and shall be equipped with universal joints to eliminate binding.</p> <p>All line pressure gauges shall be mounted in individual chrome plated castings with the identification tag recessed in the casting below the gauge. All remaining identification tags shall be mounted on the pump panel in chrome plated bezels. Mounting of the castings and identification bezels shall be done with a threaded peg cast on the back side of the bezel or screws.</p> <p><b><u>PUMP PANEL CONFIGURATION</u></b></p> <p>The pump panel configuration shall be neat and orderly.</p> <p><b><u>PUMP AND GAUGE PANEL</u></b></p> <p>The pump and gauge panels shall be constructed of aluminum with a painted FormCoat black finish. A polished aluminum trim molding shall be provided around each panel.</p> <p>The passenger's side pump panel shall be removable and fastened with swell type fasteners.</p> <p><b><u>PUMP COMPARTMENT LIGHT</u></b></p> <p>A pump compartment light shall be provided inside the right side pump enclosure and accessible through a door on the pump panel.</p> <p>A .125" weep hole shall be provided in each light lens, preventing moisture retention.</p> <p>Engine monitoring graduated LED indicators shall be incorporated with the pressure controller.</p> <p>Also provided at the pump panel shall be the following:</p> <ul style="list-style-type: none"> <li>- Master Pump Drain Control.</li> </ul> <p><b><u>ELECTRIC GAUGE HEATER</u></b></p> <p>An electric gauge heater system will be provided for all water carrying gauges and their supply tubing.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>VACUUM AND PRESSURE GAUGES</u></b></p> <p>The pump vacuum and pressure gauges shall be liquid filled and manufactured by Class 1 Incorporated ©.</p> <p>The gauges shall be a minimum of 4.00" in diameter and shall have white faces with black lettering, with a pressure range of 30.00"-0-600#.</p> <p>Gauge construction shall include a Zytel nylon case with adhesive mounting gasket and threaded retaining nut.</p> <p>The pump pressure and vacuum gauges shall be installed adjacent to each other at the pump operator's control panel.</p> <p>Test port connections shall be provided at the pump operator's panel. One (1) shall be connected to the intake side of the pump, and the other to the discharge manifold of the pump. They shall have 0.25 in. standard pipe thread connections and non-corrosive polished stainless steel or brass plugs. They shall be marked with a label.</p> <p>This gauge shall include a 10 year warranty against leakage, pointer defect, and defective bourdon tube.</p> <p><b><u>PRESSURE GAUGES</u></b></p> <p>The individual "line" pressure gauges for the discharges shall be inter-lube filled and manufactured by Class 1©.</p> <p>They shall be a minimum of 2.00" in diameter and shall have white faces with black lettering.</p> <p>Gauge construction shall include a Zytel nylon case with adhesive mounting gasket and threaded retaining nut.</p> <p>Gauges shall have a pressure range of 30"-0-400#.</p> <p>The individual pressure gauge shall be installed as close to the outlet control as practical.</p> <p>This gauge shall include a 10 year warranty against leakage, pointer defect, and defective bourdon tube.</p> <p><b><u>WATER LEVEL GAUGE</u></b></p> <p>An electronic water level gauge shall be provided on the operator's panel that registers water level by means of five colored LED lights. The lights shall be durable, ultra-bright five LED design viewable through 180 degrees. The water level indicators shall be as follows:</p> <p>- 100% = Green</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>- 75% = Yellow</p> <p>- 50% = Yellow</p> <p>- 25% = Yellow</p> <p>- Refill = Red</p> <p>The light shall flash when the level drops below the given level indicator to provide an eighth of a tank indication. To further alert the pump operator, the lights shall flash sequentially when the water tank is empty.</p> <p>The level measurement shall be based on the sensing of head pressure of the fluid in the tank.</p> <p>The display shall be constructed of a solid plastic material with a chrome plated die cast bezel to reduce vibrations that can cause broken wires and loose electronic components. The encapsulated design shall provide complete protection from water and environmental elements. An industrial pressure transducer shall be mounted to the outside of the tank. The field calibratable display measures head pressure to accurately show the tank level.</p> <p><b><u>WATER LEVEL GAUGE(S)</u></b></p> <p>There shall be one (1) water level indicator(s), Whelen, Model: PSTANK, LED module, installed at the rear of the apparatus.</p> <p>This light module shall include four (4) colored levels, and function similar to the water level indicator located at the operators panel:</p> <p>First green module indicates a full water level.</p> <p>Second blue module indicates a water level above 3/4 full.</p> <p>Third amber module indicates a water level above 1/2 full.</p> <p>Last red module indicates a water level above 1/4 full and empty.</p> <p>Above 1/4 this light shall be steady burning.</p> <p>At empty this light shall be flashing.</p> <p>This module shall be activated when the parking brake is applied.</p> <p><b><u>LIGHT SHIELD</u></b></p> <p>There shall be a polished, 16 gauge stainless steel light shield installed over the pump operator's panel.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

Bidder Complies	
Yes	No

- There shall be 12 volt DC white LED lights installed under the stainless steel light shield to illuminate the controls, switches, essential instructions, gauges, and instruments necessary for the operation of the apparatus. These lights shall be activated by the pump panel light switch. Additional lights shall be included every 18.00" depending on the size of the pump house.
- One (1) pump panel light shall come on when the pump is in ok to pump mode.

There shall be a light activated above the pump panel light switch when the parking brake is set. This is to afford the operator some illumination when first approaching the control panel.

There shall be a green pump engaged indicator light activated on at the operator's panel when the pump is shifted into gear from inside the cab.

**AIR HORN SYSTEM**

Two (2) Grover air horns shall be provided and located one (1) each side of the engine. The horn system shall be piped to the air brake system wet tank utilizing 0.38" tubing. A pressure protection valve shall be installed in-line to prevent the loss of air, in the air brake system.

**AIR HORN(s) LOCATION**

The air horn(s) location shall be in the front bumper.

**AIR HORN CONTROL**

The air horns shall be actuated by a foot switch on the officer's side and by the horn button in the steering wheel. The driver shall have the option to control the air horns or the chassis horns from the horn button by means of a selector switch located on the instrument panel.

**ELECTRONIC SIREN**

A Whelen®, Model 295SLSA1, electronic siren with noise canceling microphone shall be provided.

This siren to be active when the battery switch is on and that emergency master switch is on.

Siren head shall be located in the cab within reach of the driver.

Siren shall be actuated by a foot switch on the officer's side and by the horn button in the steering wheel. The driver shall have the option to control the siren or the chassis horns from the horn button by means of a selector switch.

**SPEAKER**

There shall be one (1) speaker provided. Each speaker shall be a Whelen model SA315P black nylon composite, 100-watt, with through bumper mounting brackets. Each speaker shall be connected to the siren amplifier.

	Bidder Complies	
	Yes	No
<p>The speaker(s) shall be recessed in the front bumper on the driver's side.</p> <p><b><u>LIGHTBAR, CAB ROOF</u></b></p> <p>One (1) 56.00" Whelen, Justice LED light bar shall be mounted on the cab roof.</p> <p>This light bar shall include the following:</p> <ul style="list-style-type: none"> <li>Four (4) red flashing CON3 LED modules facing forward.</li> <li>Two (2) white flashing CON3 LED modules facing forward.</li> <li>Two (2) red flashing LIN6 LED modules one (1) in each front corner.</li> <li>Two (2) red flashing LIN6 LED modules, one (1) in each rear corner.</li> <li>One (1) GTT Model 795 LED Opticom™, traffic light control with National standard priority.</li> </ul> <p>All lenses shall be clear.</p> <p>There will be two (2) switches located on the cab switch panel to control this lightbar.</p> <ul style="list-style-type: none"> <li>• One switch will control all warning lights.</li> <li>• One switch will control the traffic light controller.</li> </ul> <p>To meet NFPA requirements all white warning lights and the traffic light controller disabled shall be when the parking brake is applied.</p> <p><b><u>LIGHTBAR MODIFICATION</u></b></p> <p>The light bar as described elsewhere in this specification shall be modified as follows:</p> <p>The forward facing modules, beginning at the driver's side (excluding corner modules) shall be the colors listed below. The lenses shall remain clear.</p> <ol style="list-style-type: none"> <li>1. Forward facing module 1 to be RED</li> <li>2. Forward facing module 2 to be BLUE</li> <li>3. Forward facing module 3 to be RED</li> <li>4. Forward facing module 4 to be Opticom™</li> <li>5. Forward facing module 5 to be BLUE</li> <li>6. Forward facing module 6 to be RED</li> <li>7. Forward facing module 7 to be BLUE</li> <li>8. Forward facing module 8 to be RED</li> </ol>		

	Bidder Complies	
	Yes	No
<p><b><u>WARNING LIGHTS (CAB FACE)</u></b></p> <p>A pair of flush mounted Whelen model 50*03Z*R, Super 500 flashing LED lights shall be provided on the cab face or grille.</p> <p>The color of these lights shall be red Super LED/clear lens.</p> <p>A switch shall be provided inside the cab on the switch panel for actuation.</p> <p>These lights shall be installed with a chrome plated ABS plastic flange.</p> <p><b><u>HEADLIGHT FLASHER</u></b></p> <p>The high beam headlights shall flash alternately between the left and right side.</p> <p>There shall be a switch installed in the cab on the switch panel to control the high beam flash. This switch shall be live when the battery switch and the emergency master switches are on.</p> <p>The flashing shall automatically cancel when the hi-beam headlight switch is activated or when the parking brake is set.</p> <p><b><u>SIDE ZONE LOWER LIGHTING</u></b></p> <p>There shall be four (4) Whelen, Model 50*03Z*R, flashing LED lights located at the following positions:</p> <ul style="list-style-type: none"> <li>• Two (2) lights located, one (1) each side on the engine hood under 62.00" <ul style="list-style-type: none"> <li>○ The color of these lights shall be red Super LED/clear lens</li> </ul> </li> <li>• Two (2) lights located, one (1) each side on the body fender panels <ul style="list-style-type: none"> <li>○ The color of these lights shall be red Super LED/clear lens</li> </ul> </li> </ul> <p>A switch located in the cab on the switch panel shall control these lights.</p> <p>These lights shall be provided with a chrome plated ABS plastic flange</p> <p><b><u>REAR ZONE LOWER LIGHTING</u></b></p> <p>Two (2) Whelen, SUPER-LED™ model 50*03F*R flashing LED lights shall be located at the rear of the apparatus.</p> <p>The color of the lights shall be red Super LED/clear lens</p> <p>There shall be a switch located in the cab on the switch panel to control the lights.</p> <p>Each light shall be installed with a chrome plated ABS plastic flange</p>		

	Bidder Complies	
	Yes	No
<p><b><u>WARNING LIGHTS (REAR AND SIDE UPPER ZONE)</u></b></p> <p>There shall be two (2) Whelen, Model 60*02F*R, LED lights with Whelen, Model 6EFLANGE, chrome flanges provided - one light each side facing the rear.</p> <p>The LEDs and lens color of these lights shall be red Super LED/clear lens .</p> <p>Two (2) Whelen, SUPER-LED model 50*03Z*R flashing Super LED lights shall be provided at the rear of the truck in the upper zone, one light facing each side. These lights shall also be installed with chrome plated flanges.</p> <p>The LEDs and lens color of these lights shall be red Super LED/clear lens.</p> <p>There shall be a switch located in the cab to control these lights.</p> <p><b><u>TRAFFIC DIRECTING LIGHT</u></b></p> <p>There will be one (1) Whelen model TAD*, 30.36” long x 1.74” high x 2.17” deep , traffic directing light installed at the rear of the apparatus.</p> <p>The light will have six (6) amber LED lights in the center of the advisor, with one (1) red LED on one end and one (1) blue LED on the other.</p> <p>All lenses will be clear.</p> <p>The Whelen Model TADCTL1 control head will be included with this installation.</p> <p>The red and blue lights on the end will be activated with the emergency master switch.</p> <p>This traffic directing light shall be mounted at the rear of the vehicle as high as practical.</p> <p>The traffic directing light controller will be located within the switch panel in the dashboard. The controller will be within easy reach of the driver.</p> <p><b><u>LOOSE EQUIPMENT</u></b></p> <p>The following equipment shall be furnished with the completed unit:</p> <ul style="list-style-type: none"> <li>- One (1) bag of chrome, stainless steel, or cadmium plated screws, nuts, bolts and washers, as used in the construction of the unit</li> </ul> <p><b><u>NFPA REQUIRED LOOSE EQUIPMENT PROVIDED BY FIRE DEPARTMENT</u></b></p> <p>The following loose equipment as outlined in NFPA 1901, 2016 edition, section 7.9.3.1, 7.9.3.2, and 7.9.4 shall be provided by the fire department.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<ul style="list-style-type: none"> <li>• 200 ft (60 m) of 2.50" (65 mm) or larger fire hose.</li> <li>• 100 ft (120 m) of 1.50" (38 mm), 1.75" (45 mm), or 2.00" (52 mm) fire hose (if equipped with a fire pump).</li> <li>• One (1) hand line nozzle, 95 gpm (360 L/min) minimum (if equipped with a fire pump).</li> <li>• One (1) first aid kit.</li> <li>• Two (2) combination spanner wrenches.</li> <li>• One (1) hydrant wrench.</li> <li>• One (1) double female adapter, sized to fit 2.50" (65 mm) or larger fire hose.</li> <li>• One (1) double male adapter, sized to fit 2.50" (65 mm) or larger fire hose.</li> <li>• One (1) rubber mallet, for use on suction hose connections (if equipped with a fire pump).</li> <li>• One (1) traffic vest for each seating position, each vest to comply with ANSI/ISEA 207, <i>Standard for High Visibility Public Safety Vests</i>, and have a five-point breakaway feature that includes two at the shoulders, two at the sides, and one at the front.</li> <li>• Five (5) fluorescent orange traffic cones not less than 28.00" (711 mm) in height, each equipped with a 6.00" (152 mm) retro-reflective white band no more than 4.00" (152 mm) from the top of the cone, and an additional 4.00" (102 mm) retro-reflective white band 2.00" (51 mm) below the 6.00" (152 mm) band.</li> <li>• Five (5) illuminated warning devices such as highway flares, unless the five (5) fluorescent orange traffic cones have illuminating capabilities.</li> <li>• One (1) automatic external defibrillator (AED).</li> <li>• If none of the pump intakes are valved, a hose appliance that is equipped with one or more gated intakes with female swivel connection(s) compatible with the supply hose used on one side and a swivel connection with pump intake threads on the other side shall be carried. Any intake connection larger than 3.00" (75 mm) shall include a pressure relief device that meets the requirements of 16.6.6 (if equipped with pump).</li> <li>• If the apparatus does not have a 2.50" National Hose (NH) intake, an adapter from 2.50" NH female to a pump intake shall be carried, mounted in a bracket fastened to the apparatus if not already mounted directly to the intake.</li> <li>• If the supply hose carried has other than 2.50" National Hose (NH) threads, adapters shall be carried to allow feeding the supply hose from a 2.50" NH thread male discharge and to allow the hose to connect to a 2.50" NH female intake, mounted in brackets fastened to the apparatus if not already mounted directly to the discharge or intake.</li> </ul> <p><b><u>SOFT SUCTION HOSE PROVIDED BY FIRE DEPARTMENT</u></b>                      NFPA 1901, 2016 edition, section 7.8.2.1 requires a minimum of 20' of suction hose or 15' of supply hose.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>Hose is not on the apparatus as manufactured. The fire department shall provide suction or supply hose.</p> <p><b><u>DRY CHEMICAL EXTINGUISHER PROVIDED BY FIRE DEPARTMENT</u></b>                      NFPA 1901, 2016 edition, section 7.9.4 requires one (1) approved dry chemical portable fire extinguisher with a minimum 80-B:C rating mounted in a bracket fastened to the apparatus.</p> <p>The extinguisher is not on the apparatus as manufactured. The fire department shall provide and mount the extinguisher.</p> <p><b><u>WATER EXTINGUISHER PROVIDED BY FIRE DEPARTMENT</u></b>                      NFPA 1901, 2009 edition, section 7.7.3.1 requires one (1) 2.5 gallon or larger water extinguisher mounted in a bracket fastened to the apparatus.</p> <p>The extinguisher is not on the apparatus as manufactured. The fire department shall provide and mount the extinguisher.</p> <p><b><u>AXE, FLATHEAD, PROVIDED BY FIRE DEPARTMENT</u></b>                      NFPA 1901, 2009 edition, Section 7.7.3.1 requires one (1) flathead axe mounted in a bracket fastened to the apparatus.</p> <p>The axe is not on the apparatus as manufactured. The fire department shall provide and mount the axe.</p> <p><b><u>PAINT PROCESS</u></b>                      The exterior custom cab and/or body painting procedure shall consist of a seven (7) step finishing process. A commercial chassis paint process shall follow similar processes as determined by the chassis manufacturer. The following procedure shall be used by the apparatus manufacturer:</p> <ol style="list-style-type: none"> <li>1. <u>Manual Surface Preparation</u> - All exposed metal surfaces on the custom cab and body shall be thoroughly cleaned and prepared for painting. Imperfections on the exterior surfaces shall be removed and sanded to a smooth finish. Exterior seams shall be sealed before painting. Exterior surfaces that shall not be painted include; chrome plating, polished stainless steel, anodized aluminum and bright aluminum tread plate.</li> <li>2. <u>Chemical Cleaning and Pretreatment</u> - All surfaces shall be chemically cleaned to remove dirt, oil, grease, and metal oxides to ensure the subsequent coatings bond well. The aluminum surfaces shall be properly cleaned and treated using a high pressure, high temperature 4 step Acid Etch process. The steel and stainless surfaces shall be properly cleaned and treated using a high temperature 3 step process specifically designed for steel</li> </ol>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>or stainless. The chemical treatment converts the metal surface to a passive condition to help prevent corrosion. A final pure water rinse shall be applied to all metal surfaces.</p> <p>3. <u>Surfacer Primer</u> - The Surfacer Primer shall be applied to a chemically treated metal surface to provide a strong corrosion protective base coat. A minimum thickness of 2 mils of Surfacer Primer is applied to surfaces that require a critical aesthetic finish. The surfacer primer shall be a two-component high solids urethane that has excellent sanding properties and an extra smooth finish when sanded.</p> <p>4. <u>Finish Sanding</u> - The surfacer primer shall be sanded with a fine grit abrasive to achieve an ultra-smooth finish. This sanding process is critical to produce the smooth mirror like finish in the topcoat.</p> <p>5. <u>Sealer Primer</u> - The sealer primer is applied prior to the base coat in all areas that have not been previously primed with the surfacer primer. The sealer primer is a two-component high solids urethane that goes on smooth and provides excellent gloss hold out when top coated.</p> <p>6. <u>Base coat Paint</u> - Two coats of a high performance, two component high solids polyurethane base coat shall be applied. The Base coat shall be applied to a thickness that shall achieve the proper color match. The Base coat shall be used in conjunction with a urethane clear coat to provide protection from the environment.</p> <p>7. <u>Clear Coat</u> - Two (2) coats of clear coat shall be applied over the base coat color. The clear coat is a two-component high solids urethane that provides superior gloss and durability to the exterior surfaces. Lap style doors shall be clear coated to match the body. Paint warranty for the roll-up doors shall be provided by the roll-up door manufacturer.</p> <p>Specifications are written to define cyclic corrosion testing, physical strengths, durability and minimum appearance requirements must be met in order for an exterior paint finish to be considered acceptable as a quality finish.</p> <p>Each batch of base coat color shall be checked for a proper match before painting of the cab and the body. After the cab and body are painted, the color is verified again to make sure that it matches the color standard. Electronic color measuring equipment shall be used to compare the color sample to the color standard entered into the computer. Color specifications are used to determine the color match. A Delta E reading shall be used to determine a good color match within each family color.</p> <p>All removable items such as brackets, compartment doors, door hinges, and trim shall be removed and separately if required, to ensure paint behind all mounted items. Body assemblies that cannot be finish painted after assembly shall be finish painted before assembly.</p>		

	Bidder Complies	
	Yes	No
<p><b><u>PAINT - ENVIRONMENTAL IMPACT</u></b></p> <p>Contractor shall meet or exceed all current State regulations concerning paint operations. Pollution control shall include measures to protect the atmosphere, water and soil. Controls shall include the following conditions:</p> <ul style="list-style-type: none"> <li>• Topcoats and primers shall be chrome and lead free.</li> <li>• Metal treatment chemicals shall be chrome free. The wastewater generated in the metal treatment process shall be treated on-site to remove any other heavy metals.</li> <li>• Particulate emission collection from sanding operations shall have a 99.99% efficiency factor.</li> <li>• Particulate emissions from painting operations shall be collected by a dry filter or water wash process. If the dry filter is used, it shall have an efficiency rating of 98.00%. Water wash systems shall be 99.97% efficient</li> <li>• Water from water wash booths shall be reused. Solids shall be removed on a continual basis to keep the water clean.</li> <li>• Paint wastes shall be disposed of in an environmentally safe manner.</li> <li>• Empty metal paint containers shall be recycled to recover the metal.</li> <li>• Solvents used in clean-up operations shall be recycled on-site or sent off-site for distillation and returned for reuse.</li> </ul> <p>Additionally, the finished apparatus shall not be manufactured with or contain products that have ozone depleting substances. Contractor shall, upon demand, present evidence that the manufacturing facility meets the above conditions and that it is in compliance with the state EPA rules and regulations.</p> <p><b><u>COMMERCIAL CHASSIS PAINT</u></b></p> <p>The chassis shall be painted by the chassis manufacturer. It shall remain the color and commercial quality finish as provided. The primary color shall be candy apple red.</p> <p><b><u>PAINT</u></b></p> <p>The chassis shall be painted by the chassis manufacturer, and shall remain the commercial grade finish as provided. To ensure a good color match between the body and chassis, the apparatus manufacturer and chassis manufacturer shall have a mutually preapproved paint color program. The apparatus shall be painted candy apple red.</p> <p><b><u>TWO-TONE CAB</u></b></p> <p>The cab shall be painted two-tone by the apparatus manufacturer. The top portion of the cab from the bottom of the windshield up shall be painted white to match the other existing units in the Departments fleet.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p><b><u>PAINT CHASSIS FRAME ASSEMBLY</u></b>                      The chassis frame assembly shall be painted black by the chassis manufacturer. It shall remain the commercial grade finish as provided.</p> <p><b><u>COMPARTMENT INTERIOR PAINT</u></b>                      The interior of compartmentation shall be painted with a gray spatter type paint.</p> <p><b><u>REFLECTIVE STRIPES</u></b>                      Three (3) reflective stripes shall be provided along the sides of the cab and body. The reflective band shall consist of a 1.00"-6.00"-1.00" white stripe on the cab and body, with a 1.00"-6.00"-1.00" ruby red stripe on the roll-up doors. All striping shall include a 1.00" gap between stripes.                       The reflective vinyl band shall be provided across the front bumper.</p> <p><b><u>REAR CHEVRON STRIPING</u></b>                      There shall be alternating chevron striping located on the rear-facing vertical surface of the apparatus.                       The colors shall be red and L2 fluorescent yellow green.                       Each stripe shall be 6.00" in width.                       This shall meet the requirements of the current edition of NFPA 1901, which states that 50% of the rear surface shall be covered with chevron striping.</p> <p><b><u>REFLECTIVE STRIPE, CAB DOORS</u></b>                      A white reflective stripe shall be provided on the interior of each cab door.                       This stripe shall be a minimum of 96.00 square inches and shall meet the NFPA 1901 requirement.</p> <p><b><u>UNDERCOATING, CAB &amp; BODY</u></b>                      The underside of the apparatus shall be undercoated with an asphalt petroleum based material, dark in color.                       The undercoating material utilized on the apparatus shall be formulated to resist corrosion and deaden unwanted sound or road noise.                       Coating texture shall appear firm, flexible, and resistant to abrasion. Minimum dry film thickness shall be in the range of 8.00 to 12.00 mils.                       The material shall be applied to the following areas:                       Body and cab wheel well fender liners, on the back side only.</p>		

	Bidder Complies	
	Yes	No
<p>Underside of body and cab sheet metal, and structural components.</p> <p>Underside and vertical sides of all sheet metal compartmentation, including support angles.</p> <p>Structural support members under running boards, rear platforms, battery boxes, walkways, etc.</p> <p>Inside surfaces of the pump heat enclosure, (when installed).</p> <p><b><u>CD MANUAL, BODY PARTS ONLY</u></b></p> <p>A custom parts manuals for the factory installed parts only shall be provided in CD format with the completed unit.</p> <p>The manual shall contain the following:</p> <ul style="list-style-type: none"> <li>- Job number</li> <li>- Part numbers with full descriptions</li> <li>- Table of contents</li> <li>- Parts section sorted in functional groups reflecting a major system, component, or assembly</li> <li>- Parts section sorted in Alphabetical order</li> <li>- Instructions on how to locate parts</li> </ul> <p>The manual shall be specifically written for the body model being purchased. It shall not be a generic manual for a multitude of different bodies.</p> <p><b><u>SERVICE PARTS INTERNET SITE</u></b></p> <p>The service parts information included in this manual are also available on the factory website. The website offers additional functions and features not contained in this manual, such as digital photographs and line drawings of select items. The website also features electronic search tools to assist in locating parts quickly.</p> <p><b><u>MANUALS, SERVICE</u></b></p> <p>A CD format service manual supplement containing parts and service information on factory installed components shall be provided with the completed unit.</p> <p>The manual shall be specifically written for the unit being purchased. It shall not be a generic manual for a multitude of different units.</p> <p><b><u>MANUAL, CHASSIS OPERATION</u></b></p> <p>One (1) chassis operation (manufacturer's standard) shall be provided with the completed unit.</p>		

	Bidder Complies	
	Yes	No
<p><b><u>ONE (1) YEAR MATERIAL AND WORKMANSHIP</u></b>                      Each new piece of apparatus shall be provided with a minimum one (1) year basic apparatus material and workmanship limited warranty. The warranty shall cover such portions of the apparatus built by the manufacturer as being free from defects in material and workmanship that would arise under normal use and service.</p> <p>A copy of the warranty certificate shall be submitted with the bid package (No Exception).</p> <p><b><u>CHASSIS WARRANTY</u></b>                      The chassis manufacturer shall provide a <b>five (5) year or 100,000 mile warranty.</b></p> <p><b><u>PAINT WARRANTY</u></b>                      The commercial chassis manufacturer's paint warranty shall apply to the paint on the chassis only.</p> <p><b><u>CAMERA SYSTEM WARRANTY</u></b>                      A fifty four (54) month warranty shall be provided for the camera system.</p> <p><b><u>COMPARTMENT LIGHT WARRANTY</u></b>                      A ten (10) year material and workmanship limited warranty shall be provided for the 12 volt DC LED strip lights. The warranty shall cover the LED strip lights to be free from defects in material and workmanship that would arise under normal use.</p> <p>A copy of the warranty certificate shall be submitted with the bid package (no exception).</p> <p><b><u>TRANSMISSION WARRANTY</u></b>                      The transmission shall have a <b>five (5) year/unlimited mileage</b> warranty covering 100 percent parts and labor. The warranty to be provided by Allison Transmission and not apparatus builder.</p> <p><b><u>TEN (10) YEAR STRUCTURAL INTEGRITY</u></b>                      Each new piece of apparatus shall be provided with a <b>ten (10) year</b> material and workmanship limited warranty on the apparatus body. The warranty shall cover such portions of the apparatus built by the manufacturer as being free from defects in material and workmanship that would arise under normal use and service.</p> <p>A copy of the warranty certificate shall be submitted with the bid package (no exception).</p> <p><b><u>ROLL UP DOOR MATERIAL AND WORKMANSHIP WARRANTY</u></b>                      A roll-up door limited warranty shall be provided. The roll-up door shall be warranted against manufacturing defects for a period of <b>ten (10) years</b>. A <b>five (5) year</b> limited warranty shall be provided on painted roll up doors.</p>		

3000 GALLON TANKER - BRISTOL KENDALL FIRE PROTECTION DISTRICT

	Bidder Complies	
	Yes	No
<p>A copy of the warranty certificate shall be submitted with the bid package (no exception).</p> <p><b><u>PUMP WARRANTY</u></b>                      A <b>five (5) year</b> limited warranty on parts and <b>two (2) year</b> limited warranty on labor shall be provided for the pump.</p> <p>A copy of the warranty certificate shall be submitted with the bid package (no exception).</p> <p><b><u>TEN (10) YEAR PUMP PLUMBING WARRANTY</u></b>                      The stainless steel plumbing components and ancillary brass fittings used in the construction of the water/foam plumbing system shall be warranted for a period of <b>ten (10) years or 100,000 miles</b>. This covers structural failures caused by defective design or workmanship, or perforation caused by corrosion, provided the apparatus is used in a normal and reasonable manner. This warranty is extended only to the original purchaser for a period of ten years from the date of delivery.</p> <p>A copy of the warranty certificate shall be submitted with the bid package (no exception).</p> <p><b><u>WATER TANK LIFETIME MATERIAL AND WORKMANSHIP</u></b>                      The poly water tank, shall be provided with a lifetime material and workmanship limited warranty.</p> <p>A copy of the warranty certificate shall be submitted with the bid package (no exception).</p> <p><b><u>TEN (10) YEAR PAINT AND CORROSION</u></b>                      Apparatus shall be provided with a <b>ten (10) year</b> paint and corrosion limited warranty on the apparatus body. The warranty shall cover painted exterior surfaces of the body to be free from blistering, peeling, corrosion, or any other adhesion defect caused by defective manufacturing methods or paint material selection that would arise under normal use and service.</p> <p>A copy of the warranty certificate shall be submitted with the bid package (no exception).</p> <p><b><u>VEHICLE STABILITY CERTIFICATION</u></b>                      The fire apparatus manufacturer shall provide a certification stating the apparatus complies with NFPA 1901, current edition, section 4.13, Vehicle Stability. The certification shall be provided at the time of bid.</p> <p><b><u>CAB INTEGRITY</u></b>                      The cab has been tested to and passed the following standards:</p> <ul style="list-style-type: none"> <li>- ECE Regulation No.29</li> <li>- SAE J2422 Cab Roof Strength Evaluation - Quasi-Static Loading Heavy Trucks.</li> </ul>		

	Bidder Complies	
	Yes	No
<p><b><u>AMP DRAW REPORT</u></b></p> <p>The bidder shall provide, at the time of bid and delivery, an itemized print out of the expected amp draw of the entire vehicle's electrical system.</p> <p>The manufacturer of the apparatus shall provide the following:</p> <ul style="list-style-type: none"> <li>• Documentation of the electrical system performance tests.</li> <li>• A written load analysis, which shall include the following: <ul style="list-style-type: none"> <li>○ The nameplate rating of the alternator.</li> <li>○ The alternator rating under the conditions specified per: <ul style="list-style-type: none"> <li>▪ Applicable NFPA 1901 or 1906 (Current Edition).</li> </ul> </li> <li>○ The minimum continuous load of each component that is specified per: <ul style="list-style-type: none"> <li>▪ Applicable NFPA 1901 or 1906 (Current Edition).</li> </ul> </li> <li>○ Additional loads that, when added to the minimum continuous load, determine the total connected load.</li> <li>○ Each individual intermittent load.</li> </ul> </li> </ul> <p>All of the above listed items shall be provided by the bidder per the applicable NFPA 1901 or 1906 (Current Edition).</p>		